

ITS Intertek Testing Services
ETL SEMKO

8431 Murphy Drive
Middleton, WI 53562

**ITS TEST REPORT #J99031218-231
TEST OF A WOOD BURNING STOVE
FOR EMISSIONS & EFFICIENCY USING
EPA METHOD 28 AND 5G-3
MODEL: SQUIRREL
WOOD BURNING STOVE
FOR
MORSO JERNSTOBERI A/S
FURVEJ 6 7900 NYKOBING
MORS, DENMARK**

Intertek Testing Services

Report Date: February 8, 1999 Report #: J99031218-231
Client: Morso Jernstoberi A/S Model: 1410 Squirrel

Page 1 of 19

TEST OF A WOOD BURNING STOVE
FOR

EMISSIONS AND EFFICIENCY

PER

EPA METHODS 28 AND 5G-3

FOR

MORSO JERNSTOBERI A/S
FURVEJ 6 7900 NYKOBING
MORS, DENMARK 7900

TESTED BY:

INTERTEK TESTING SERVICES NA INC.
8431 MURPHY DRIVE
MIDDLETON, WISCONSIN 53562

TEST DATES: FEBRUARY 3-8, 2000
REPORT DATE: FEBRUARY 11, 2000

All services undertaken are subject to the following general policy: Reports are submitted for exclusive use of the clients to whom they are addressed. Their significance is subject to the adequacy and representative character of the samples and to the comprehensiveness of the tests, examinations, or surveys made. No quotations from reports or use of the Intertek Testing Services NA name, logo, or registered (WH) mark is permitted except as expressly authorized by Intertek Testing Services NA Inc. in writing.

Intertek Testing Services

Report Date: February 8, 1999 Report #: J99031218-231
Client: Morso Jernstoberi A/S Model: 1410 Squirrel

Page 2 of 19

I. INTRODUCTION

A.	General	4
B.	Test Unit Description	4
C.	Results	4
D.	Pretest Information	5
E.	Report Organization	5

II. SUMMARY OF TEST RESULTS

A.	Emissions	6
B.	Weighted Average Calculation	6
C.	Test Facility Conditions	7
D.	Fuel Qualities	7
E.	Dilution Tunnel Flow Rate Measurement and Sampling Data (5G-3)	8
F.	Dilution Tunnel Dual Train Precision	8
G.	General Summary of Results	9

III. PROCESS DESCRIPTION

A.	Discussion	9
B.	Unit Dimensions	10
C.	Air Supply System	10
D.	Operation during Test	10
E.	Start-Up Operation	11

IV. SAMPLING SYSTEMS

A.	Sampling Locations	11
	1. Dilution Tunnel (Figure 1)	12
B.	Operational Drawings	
	1. Stack Gas Sample Train (Figure 2)	13
	2. Dilution Tunnel Sample Systems (Figure 3)	14
C.	Equipment List	15

V. SAMPLING METHODS

A.	Particulate	16
B.	Efficiency	16

Intertek Testing Services

Report Date: February 8, 1999 Report #: J99031218-231
Client: Morso Jernstoberi A/S Model: 1410 Squirrel

Page 3 of 19

VI. QUALITY ASSURANCE

A.	Instrument Calibration	
	1. Dry Gas Meters	16
	2. Stack Sample rotometer	16
	3. Gas Analyzers	17
B.	Test Method Procedures	
	1. Leak Check Procedures.....	18
	2. Tunnel Velocity / Flow Measurement	18
	3. PM Sampling System Proportionality (5G-3)	18

VII. PHOTOGRAPHS

VIII. APPENDICES

Data and Calculation Forms.....	A
Laboratory Operating Procedure.....	B
Sampling Proportionality Results	C
Dry Gas Meter Calibration Data	D
Other Calibration Data	E
Drawings and Specifications.....	F
Operators Manual.....	G
Calculation Procedures and Sample Calculations.....	H
Efficiency and Heat Output Results.....	I
Unit Pre-Burn Documentation	J

Intertek Testing Services

Report Date: February 8, 1999 Report #: J99031218-231

Page 4 of 19

Client: Morso Jernstoberi A/S Model: 1410 Squirrel

I. INTRODUCTION

I.A. GENERAL

From February 3 through 8, 2000 Intertek Testing Services NA Inc. (ITS) conducted tests on Morso Jernstoberi's model 1410 (Squirrel) wood burning stove to determine compliance with U.S. EPA emissions regulations.

Tests were conducted by Rick Armstrong. Present, as an observer for tests was Karsten Aagaard, a representative of Morso. The tests were conducted at the Intertek Testing Services NA Inc. laboratory located at 8431 Murphy Drive, Middleton, Wisconsin. The laboratory elevation is 860 feet above sea level. Tests were conducted to EPA Method 28 and 5G-3 criteria.

I.B. TEST UNIT DESCRIPTION

The Morso Squirrel model 1410 wood burning stove is rectangular in shape and sits on four legs. The Unit is constructed from cast iron with a glass and cast iron door that is hinged on the left. The air control consists of a spin type damper located on the door above the glass. The air is directed down the glass as air wash. The firebox is lined on the sides with cast refractory. Under the firebox is an ash-pan.

I.C. RESULTS

The unit as tested produced a weighted-average emissions rate of 3.313 grams/hour and did not exceed any of the emissions rate caps specified in the EPA regulations. The unit thus meets EPA certification requirements for 1990.

Intertek Testing Services

Report Date: February 8, 1999 Report #: J99031218-231

Page 5 of 19

Client: Morso Jernstoberi A/S Model: 1410 Squirrel

I.D. PRETEST INFORMATION

The test unit was received at Intertek Testing Services NA Inc. in Middleton, Wisconsin on December 29, 1999 via KLM. The unit was inspected upon receipt and found to be in good condition. The unit was set up following the manufacturer's instructions without difficulty. Following assembly, the unit was placed on the test stand and instrumented with thermocouples located centrally on the top, back, left, right, and bottom. Prior to beginning the emissions tests the unit was operated for a minimum of 10 hours at high-to-medium burn rates. The unit was found to be operating satisfactory during this break-in. The 13 plus hours of pre-burning was conducted on January 31 and February 1, 2000. The fuel used for the break-in process is all Red Oak cordwood with Douglas Fir scrap as kindling. The moisture content of the cordwood was 16-20% on the wet basis.

Following the pre-burn break-in process, the unit was allowed to cool. The chimney system and laboratory dilution tunnel was cleaned using standard wire brush chimney cleaning equipment.

On February 3, 2000, the unit was ready for testing.

I.E. REPORT ORGANIZATION

This report includes summaries of all data necessary to determine compliance with the regulations. Raw data, calibration records, intermediate calculations, drawings and specifications and other supporting information are contained in appendices to this report.

Intertek Testing Services

Report Date: February 8, 1999 Report #: J99031218-231

Page 6 of 19

Client: Morso Jernstoberi A/S Model: 1410 Squirrel

II. SUMMARY OF TEST RESULTS

II.A. EMISSIONS

Run Number	Test Date	Burn Rate (kg/hr)	Emission Rate (g/hr)	Adjusted Emission Rate (g/hr)	Heating Efficiency** (% Overall)
1	2/3/00	0.795	4.523	6.369	70.61
2	2/4/00	0.986	1.390	2.392	65.52
3	2/7/00	1.395	0.718	1.383	65.52
4	2/8/00	1.826	2.831	4.317	66.79

**Calculated as specified in CSA B-415

II.B. WEIGHTED AVERAGE CALCULATION

Run Number	Burn Rate	(E)		(K)			Prob	Factor	(KxE)	(KxOHE)
		Adjusted Emission Rate g/hr	Output (OHE)*(BTU/HR)	Weighting	Factor	Factor				
1	0.795	6.369	70.61	9586.27	.2165	.3654	2.3275	25.80		
2	0.986	2.392	65.37	11889.39	.3654	.4744	1.1348	31.01		
3	1.395	1.383	65.52	16821.19	.6909	.5132	.7098	33.62		
4	1.826	4.317	66.79	22018.27	.8786	.3091	1.3344	20.64		
Sums:						1.66214	5.5064	111.08		

Weighted Average Emissions Rate: $5.5064 \div 1.66214 = 3.3128$

Weighted Average Overall Heating Efficiency: $111.08 \div 1.66214 = 66.83\%$

*Calculated as specified in CSA B-415

Intertek Testing Services

Report Date: February 8, 1999 Report #: J99031218-231

Page 7 of 19

Client: Morso Jernstoberi A/S Model: 1410 Squirrel

II.C. TEST FACILITY CONDITIONS

Run Number	Room Temperature		Barometric Pressure		Relative Humidity		Air Velocity	
	Before	After	Before	After	Before	After	Before	After
	(F)		(in. Hg)		(%)		(ft/min)	
1	73	74	28.73	28.78	33	34	0	0
2	73	74	29.22	29.28	35	28	0	0
3	68	75	29.34	29.40	41	30	0	0
4	71	75	29.40	29.38	32	25	0	0

II.D. FUEL QUALITIES

Run Number	Pre-Test Load			Test Load					
	Loading Weight	Moisture Content	Coal Bed Weight	Weight	Density	Moisture Content	Piece Length	Number of	
	Wet Basis (lb.)	Dry Basis (%)	(lb.)	Wet Basis (lb.)	Wet Basis (lbs/ft ³)	Dry Basis (%)	(in.)	2x4's	4x4's
1	4.89	24.54	1.1	5.1	6.929	22.03	10.00	3	0
2	5.08	21.24	1.1	5.22	7.090	23.18	10.00	3	0
3	5.15	20.85	1.1	5.16	7.011	22.79	10.00	3	0
4	5.31	19.31	1.1	5.36	7.283	22.92	10.00	3	0

Intertek Testing Services

Report Date: February 8, 1999 Report #: J99031218-231

Page 8 of 19

Client: Morso Jernstoberi A/S Model: 1410 Squirrel

.E. DILUTION TUNNEL FLOW RATE MEASUREMENTS AND SAMPLING DATA (5G-3)

Average Dilution Tunnel Measurements					Sample Data			
Run Number	Burn Time (min)	Velocity (ft/sec)	Volumetric Flow Rate (dscf/min)	Total Temp. (°R)	Sample Volume (dscf)		Particulate Catch (mg)	
					1	2	1	2
1	143	13.51	142.99	542.00	32.73	33.29	17.3	17.5
2	117	13.38	143.89	542.38	27.58	27.70	4.3	4.6
3	82	13.57	143.97	552.20	19.15	19.34	1.6	1.6
4	65	13.46	142.50	553.50	15.25	15.55	5.1	5.1

I.F. DILUTION TUNNEL DUAL TRAIN PRECISION

Run Number	Sample Ratios		Total Emissions (grams)		% Deviation
	Train 1	Train 2	Train 1	Train 2	
1	624.81	614.28	10.81	10.75	0.46
2	610.33	607.88	2.62	2.80	5.26
3	616.41	610.53	0.99	0.98	0.79
4	607.23	595.58	3.10	3.04	1.61

Intertek Testing Services

Report Date: February 8, 1999 Report #: J99031218-231

Page 9 of 19

Client: Morso Jernstoberi A/S Model: 1410 Squirrel

I.G.

GENERAL SUMMARY OF RESULTS

Run Number	Burn Rate (kg/hr)	Average Temperature (F) Combustion	In Surface Temperature (F) Surface	Change In Surface Temperature (F)	Initial Draft (in. H ₂ O)	Primary Air Setting	Run Time (min)	Average Draft (in. H ₂ O)
1	0.795	772.38	441.43	-113.80	.045	1 turn open	143	.043
2	0.986	828.54	482.02	-65.40	.040	1¼ turns	117	.049
3	1.395	957.50	544.10	-18.6	.072	2 1/2 turns	82	.067
4	1.826	1063.13	580.40	+ 30.80	.053	full open	65	.073

Intertek Testing Services

Report Date: February 8, 1999 Report #: J99031218-231
Client: Morso Jernstoberi A/S Model: 1410 Squirrel

Page 10 of 19

III. PROCESS DESCRIPTION

III.A. DISCUSSION

RUN #1 (February 3, 2000) the air control was set at one turn from full closed. The test was loaded in 35 seconds. The door was open for 3 minutes and the air control was open for 5 minutes. Burn time was 143 minutes making the burn rate 0.795 kg/hour, a category 1-burn rate. At 13:52 the fire was stirred and the door was open for 15 seconds. See sec. 6.4.3

RUN #2 (February 4, 2000) the air control was set at 1¼ turns from closed. The test was loaded in 25 seconds. The door was open for 5 minutes. The air control was not adjusted during start-up. Burn time was 117 minutes for a category 2-burn rate of .986 kg/hr.

RUN #3 (February 7, 2000) the air control was set to 2 ½ turns from closed. The test was loaded in 30 seconds, the door was open for 5 minutes. The air was not adjusted during start up. Burn time was 82 minutes for a category 3-burn rate of 1.395 kg/hr.

RUN #4 (February 8, 2000) the primary air control was set at full open. The test was loaded in 15 seconds. The door was open for 3 minutes. Burn time was 65 minutes for a category 4-burn rate of 1.826 kg/hr.

Intertek Testing Services

Report Date: February 8, 1999 Report #: J99031218-231
Client: Morso Jernstoberi A/S Model: 1410 Squirrel

Page 11 of 19

III.B. UNIT DIMENSIONS

28.25" high, 22.5" wide and 19.5" deep.

III.C. AIR SUPPLY SYSTEM

Primary combustion air enters the unit through a spin type damper centrally located on the door above the glass. This air is directed down across the glass as air wash. Secondary air is channeled uncontrolled up the rear of the firebox and forward in the baffle where it spills out **through 48 holes**. Combustion products then exit the unit through a six-inch flue collar located centrally at the rear of the stovetop.

III.D. OPERATION DURING TEST

The stove and all lab equipment operated as they should during all tests.

Intertek Testing Services

Report Date: February 8, 1999 Report #: J99031218-231

Page 12 of 19

Client: Morso Jernstoberi A/S Model: 1410 Squirrel

III.E. START-UP OPERATION

Each test was started with a clean firebox and the scale zeroed. A fire was started using newspaper and Douglas Fir scraps for kindling. For all tests the fire was started with two to three pounds of kindling and then a warm-up pre-test load of fuel was put in. This was allowed to burn until there was about one to two lbs. of fuel was left. At this point, the stove was cleaned out the scale was zeroed. Approximately 1 lb. of hot coals from the warm-up fire was put back in to start the pre-burn fuel. Pretest loads were fired on high until burning well. Stirring was done as required to insure uniform charcoalization. At least one hour prior to reloading the air controls was set to the approximate position used during the test. Stirring was limited to less than 1 minute during the last 15 minutes of the pre-test.

IV. SAMPLING SYSTEMS

IV.A. SAMPLING LOCATIONS

Particulate samples are collected from the dilution tunnel at a point 20 feet from the tunnel entrance. The tunnel has two elbows and two mixing baffles in the system ahead of the sampling section. (See Figure 3.) The sampling section is a continuous 13 foot section of 6 inch diameter pipe straight over its entire length. Tunnel velocity pressure is determined by a standard Pitot tube located 60 inches from the beginning of the sampling section. The dry bulb thermocouple is located six inches downstream from the Pitot tube. Tunnel samplers are located 60 inches downstream of the Pitot tube and 36 inches upstream from the end of this section. (See Figure 1.)

Stack gas samples are collected from the steel chimney section 8 feet \pm 6 inches above the scale platform. (See Figure 2.)

Intertek Testing Services

Report Date: February 8, 1999 Report #: J99031218-231

Page 13 of 19

Client: Morso Jernstoberi A/S Model: 1410 Squirrel

IV.A.(1) DILUTION TUNNEL




FIGURE 1


Intertek Testing Services

Report Date: February 8, 1999 Report #: J99031218-231
Client: Morso Jernstoberi A/S Model: 1410 Squirrel

Page 14 of 19

IV.B. OPERATIONAL DRAWINGS

IV.B.(1) STACK GAS SAMPLE TRAIN



ITS FLUE GAS SAMPLE TRAIN

FIGURE 2

IV.B.(2). DILUTION TUNNEL SAMPLE SYSTEMS




Figure 3

Intertek Testing Services

Report Date: February 8, 1999 Report #: J99031218-231
 Client: Morso Jernstoberi A/S Model: 1410 Squirrel

Page 16 of 19

IV.B. EMISSION AND EFFICIENCY EQUIPMENT LIST

<u>ITEM DESCRIPTION</u>	<u>MANUFACTURER</u>	<u>MODEL</u>	<u>SERIAL #</u>
1. CO2 Analyzer (WHI#010)	HORIBA	PIR-2000	607023
2. CO Analyzer (WHI #009)	HORIBA	PIR-2000	6110019
3. O2 Analyzer (WHI #011)	BECKMAN	755	1001926
4. Dry Gas Meter (WHI #012)	Rockwell	T-110	26866
5. Dry Gas Meter (WHI #013)	Rockwell	T-110	26873
6. Rotometer (WHI # 015)	Matheson	602 Tube	
7. Rotometer (3) (WHI # 016)	Matheson	603 Tube	
8. Rotometer (2) (WHI # 019)	Matheson	604 Tube	
9. Hot Wire Anemometer (WHI #021)	Alnor	8525	MD 1057
10. Inclined Manometer (WHI #022)	Dwyer	125-AV	
11. Pitot Tube (WHI # 044)			
12. Manometer 0-10" (WHI #024)	Dwyer	400-10	
13. Mercury Barometer (WHI # 142)	Meriam	310EC10WM	184550-XI
14. Draft Indicator (WHI #027)	Dwyer	2000-00	R60825 M29
15. Scale, 1000# Cap./Record.(WHI #025)	Toledo Masstron	ML222	8013
16. Readout for 1000# Scale (WHI #007)	NCI	5780	C800174
17. Scale, 75# Capacity (WHI #006)	NCI	3824-100	762117
18. Readout for 75# Scale (WHI #008)	NCI	5780	G800082
19. Analytical Balance (WHI #028)	OHAUS	G-110	5336
20. Dial-o-gram Balance 2610 g (WHI # 031)	OHAUS	1650	
21. Audit Weights 1 mg-100 g/Class-S (WHI # 029)	Ainsworth	4254-S	39392
22. Diaphragm Pumps (4) (WHI # 032 - 035)	Dayton	ZO24 (1) 2Z866 (3)	
23. Method 5H Glassware (WHI # 036)	Andersen	4" Filter, 4-250 ml Impingers	
24. Gases; Calibration, Zero, Span	Matheson		
25. Regulators for Gases (6) (WHI # 037 - 043)	Matheson	8-(XXXX)	
26. High Accuracy Needle Valves (9)	Matheson		
27. Solenoid Valves (12) (WHI # 045)	Dayton		
28. Switches (Misc.) (WHI # 045)	Dayton		
29. ORSAT Gas Analyzer (WHI # 048)	Fisher	D	
30. Oxygen Bomb Calorimeter (WHI # 047)	Parr	1341	4514
31. Moisture Meter (WHI #049)	Delmhorst	RC-1C	14356
32. Humidity Chamber (WHI # 050)	Lab Built		
33. Dilution Tunnel (WHI # 046)	Lab Built		
34. Spirometer (WHI # 51)	Lab Built		
35. Data Acquisition System (WHI # 052)	Lab Built		
36. Drying Oven (WHI # 002)	Blue-M	SW-11TA-1	SW-291
37. Filter Holders, 47-mm (8) (WHI # 053)	Nalgene		
38. Type-K Meter (WHI #054)	Omega	199	21662
39. Digital Voltmeter (WHI # 055)	Newport	2004-3	6090022-3
40. Type K Thermocouple Wire 24 Ga.	Gordon	Special Limits of Error	
41. Type K T/C Plugs	Gordon	K-901/900	
42. Dry Gas Meter (WHI #014)	Rockwell	T-110	27002
43. Audit Weights; 5#, 10# (WHI # 160)	Rice Lake Weighing System		Class-F
44. Sling Psychrometer (WHI # 126)	Taylor		
45. Chart Recorder (WHI # 056)	Cole-Palmer	2030-0000	221063
46. Infrared Pyrometer (WHI #102)	Omega	OS-2000A	A4048T
47. Class C Weights 1-500 g (WHI # 161)	Ohaus		
48. Bomb Calorimeter Thermometer (WHI # 162)	Parr	1603	3K9347
49. Microtector Gauge (WHI # 103)	Dwyer	1430	
50. Bubble flow meter (WHI # 415)	Humonics	650	570192
51. Soxhlet extractor (WHI # 413)	Fisher Scientific		
52. ESS Unit (WHI # 416)	Omni		
53. Unimantle (WHI # 413)			
54. Magnehelic (WHI #027)			

Prepared January 1988 by Rick Curkeet / Rev. May1997 by Rick Armstrong

Intertek Testing Services

Report Date: February 8, 1999 Report #: J99031218-231

Page 17 of 19

Client: Morso Jernstoberi A/S Model: 1410 Squirrel

V. SAMPLING METHODS

V.A. PARTICULATE SAMPLING

Particulates were sampled in strict accordance with EPA Method 5G-3. This method uses two identical sampling systems with Gelman A/E 61631 binder free, 47-mm diameter filters. The dryers used in the sample systems are filled with "Drierite" before each test run.

V.B. EFFICIENCY

Efficiencies reported were based on Method CSA-B415 (calculation). Stack gas analysis for oxygen, carbon dioxide and carbon monoxide was performed in accordance with EPA Method 5H.

VI. QUALITY ASSURANCE

VI.A. INSTRUMENT CALIBRATION

VI.A.(1). DRY GAS METERS

At the conclusion of each test program the dry gas meters are checked against our standard dry gas meter. Three runs are made on each dry gas meter used during the test program. The average calibration factors obtained are then compared with the six-month calibration factor and, if within 5%, the six-month factor is used to calculate standard volumes. Results of this calibration are contained in Appendix D.

An integral part of the post test calibration procedure is a leak check of the pressure side by plugging the system exhaust and pressurizing the system to 10" W.C. The system is judged to be leak free if it retains the pressure for at least 10 minutes.

The standard dry gas meter is calibrated every 6 months using a Spirometer designed by the EPA Emissions Measurement Branch. The process involves sampling the train operation for 1 cubic foot of volume. With readings made to .001 ft³, the resolution is .1%, giving an accuracy higher than the $\pm 2\%$ required by the standard.

VI.A.(2). STACK SAMPLE ROTAMETER

The stack sample rotometer is checked by running three tests at each flow rate used during the test program. The flow rate is checked by running the rotometer in series with one of the dry gas meters for 10 minutes with the rotometer at a constant setting. The dry gas meter volume measured is then corrected to standard temperature and pressure conditions. The flow rate determined is then used to calculate actual sampled volumes.

Intertek Testing Services

Report Date: February 8, 1999 Report #: J99031218-231

Page 18 of 19

Client: Morso Jernstoberi A/S Model: 1410 Squirrel

VI.A.(3). GAS ANALYZERS

The continuous analyzers are zeroed and spanned before each test with appropriate gases. A mid-scale multi-component calibration gas is then analyzed (values are recorded). At the conclusion of a test, the instruments are checked again with zero, span and calibration gases (values are recorded only). The drift in each meter is then calculated and must not exceed 5% of the scale used for the test.

At the conclusion of each unit test program, a five-point calibration check is made. This calibration check must meet accuracy requirements of the applicable standards. Consistent deviations between analyzer readings and calibration gas concentrations are used to correct data before computer processing. Data is also corrected for interferences as prescribed by the instrument manufacturers instructions. Calibration gases are checked by ORSAT analysis when received to verify suppliers analysis.

Intertek Testing Services

Report Date: February 8, 1999 Report #: J99031218-231
Client: Morso Jernstoberi A/S Model: 1410 Squirrel

Page 19 of 19

VI.B. TEST METHOD PROCEDURES

VI.B.(1). LEAK CHECK PROCEDURES

Before and after each test, each sample train is tested for leaks. Leakage rates are measured and must not exceed 0.02 CFM or 4% of the sampling rate. Leak checks are performed checking the entire sampling train, not just the dry gas meters. Pre-test and post-test leak checks are conducted with a vacuum of 10 inches of mercury. Vacuum is monitored during each test and the highest vacuum reached is then used for the post test vacuum value. If leakage limits are not met, the test run is rejected. During, these tests the vacuum was typically less than 2 inches of mercury. Thus, leakage rates reported are expected to be much higher than actual leakage during the tests.

VI.B.(2). TUNNEL VELOCITY/FLOW MEASUREMENT

The tunnel velocity is calculated from a center point pitot tube signal multiplied by an adjustment factor. This factor is determined by a traverse of the tunnel as prescribed in EPA Method 1. Final tunnel velocities and flow rates are calculated from EPA Method 2, Equation 6.9 and 6.10. (Tunnel cross sectional area is the average from both lines of traverse.)

Pitot tubes are cleaned before each test and leak checks are conducted after each test.

VI.B.(3). PM SAMPLING PROPORTIONALITY (5G-3)



Proportionality was calculated in accordance with EPA Method 5G-3. The data and results are included in Appendix C.

All tests were conducted, analyzed, and reported on by:



Rick Armstrong, Engineering Technician

Reviewed By:


Edwin Hodgson, Project Manager
William Keen, Engineering Technician

Intertek Testing Services

Report Date: February 8, 2000
Client: Morso Jernstoberi A/S

Report #: 99031218-231
Model: 1410 Squirrel

Photograph Page 1 of 5



Intertek Testing Services

Report Date: February 8, 2000
Client: Morso Jernstoberi A/S

Report #: 99031218-231
Model: 1410 Squirrel

Photograph Page 2 of 5



Intertek Testing Services

Report Date: February 8, 2000
Client: Morso Jernstoberi A/S

Report #: 99031218-231
Model: 1410 Squirrel

Photograph Page 3 of 5



Intertek Testing Services

Report Date: February 8, 2000
Client: Morso Jernstoberi A/S

Report #: 99031218-231
Model: 1410 Squirrel

Photograph Page 4 of 5



Intertek Testing Services

Report Date: February 8, 2000
Client: Morso Jernstoberi A/S

Report #: 99031218-231
Model: 1410 Squirrel

Photograph Page 5 of 5



APPENDIX A

Intertek Testing Services

SFBA EPA ADJUSTED EMISSION RESULTS

Manufacturer:	Morso	RESULTS	
Model:	1410		
Date:	02/03/00	AVERAGE ADJUSTED EMISSION R	6.369
Run:	1		
Project #:	31218	Burn Rate (Dry kg/hr):	0.795
Test Duration: (minutes)	143		
PRESSURE FACTOR:		0.96106	BAROMETRIC PRESSURE
TEMPERATURE FACTORS		Average: 28.755	
		Start: 28.73	
		End: 28.78	
DGM #1:	0.97772		
DGM #2:	0.98022		
DRY GAS METER VALUES			
VOLUMES SAMPLED		DGM #1	Final: 140.757
DGM #1:	32.72651	Initial:	106.467
DGM #2:	33.28749		
		DGM #2	Final: 518.210
TOTAL TUNNEL VOLUME (scf):	20447.986	Initial:	484.106
SAMPLE RATIOS		TEMPERATURES (DEG. RANKIN)	
Sample Train 1:	624.814	DGM #1:	540.031
Sample Train 2:	614.284	DGM #2:	538.656
TOTAL EMISSIONS		CALIBRATION FACTORS	
Sample Train 1 (g):	10.8093	DGM #1:	1.0157
Sample Train 2 (g):	10.7500	DGM #2:	1.0361
EMISSION RATES		TUNNEL FLOW RATE:	
Sample Train 1 (g/hr):	4.5354	142.993	
Sample Train 2 (g/hr):	4.5105		
ADJUSTED EMISSION RATES		PARTICULATE CATCH (mg)	
Sample Train 1 (g/hr):	6.3835	Sample Train 1:	17.3
Sample Train 2 (g/hr):	6.3544	Sample Train 2:	17.5
DEVIATION:	0.46%		

Intertek Testing Services

SFBA EPA ADJUSTED EMISSION RESULTS

Manufacturer:	Morso	RESULTS
Model:	1410	
Date:	02/04/00	AVERAGE ADJUSTED EMISSION R/ 2.392
Run:	2	
Project #:	31218	Burn Rate (Dry kg/hr): 0.986
Test Duration (minutes):	117	

PRESSURE FACTOR:	0.97761	BAROMETRIC PRESSURE	Average:	29.25
TEMPERATURE FACTORS			Start:	29.22
DGM #1:	0.98522		End:	29.28
DGM #2:	0.98226			

VOLUMES SAMPLED		DRY GAS METER VALUES		
DGM #1:	27.58444	DGM #1	Final:	168.970
DGM #2:	27.69573		Initial:	140.773
TOTAL TUNNEL VOLUME (scf):	16835.692	DGM #2	Final:	546.063
			Initial:	518.226

SAMPLE RATIOS:		TEMPERATURES (DEG. RANKIN)		
Sample Train 1:	610.333	DGM #1:	535.923	
Sample Train 2:	607.880	DGM #2:	537.538	

TOTAL EMISSIONS		CALIBRATION FACTORS		
Sample Train 1 (g):	2.6244	DGM #1:	1.0157	
Sample Train 2 (g):	2.7963	DGM #2:	1.0361	

EMISSION RATES		TUNNEL FLOW RATE:	143.895	
Sample Train 1 (g/hr):	1.3459	PARTICULATE CATCH (mg)		
Sample Train 2 (g/hr):	1.4340	Sample Train 1:	4.3	

ADJUSTED EMISSION RATES		Sample Train 2:	4.6	
Sample Train 1 (g/hr):	2.3289			
Sample Train 2 (g/hr):	2.4547			

DEVIATION: 5.26%

Intertek Testing Services

SFBA EPA ADJUSTED EMISSION RESULTS

Manufacturer:	Morso	RESULTS	
Model:	1410		
Date:	02/07/00	AVERAGE ADJUSTED EMISSION R/	1.383
Run:	3		
Project #:	31218	Burn Rate (Dry kg/hr):	1.395
Test Duration: (minutes)	82		

PRESSURE FACTOR:	0.98162	BAROMETRIC PRESSURE	
TEMPERATURE FACTORS		Average:	29.37
DGM #1:	0.97841	Start:	29.34
DGM #2:	0.98178	End:	29.4

VOLUMES SAMPLED		DRY GAS METER VALUES	
DGM #1:	19.15209	DGM #1	Final: 188.630
DGM #2:	19.33636		Initial: 168.997
TOTAL TUNNEL VOLUME (scf):	11805.486	DGM #2	Final: 565.450
			Initial: 546.085

SAMPLE RATIOS		TEMPERATURES (DEG. RANKIN)	
Sample Train 1:	616.407	DGM #1:	539.650
Sample Train 2:	610.533	DGM #2:	537.800

TOTAL EMISSIONS		CALIBRATION FACTORS	
Sample Train 1 (g):	0.9863	DGM #1:	1.0157
Sample Train 2 (g):	0.9769	DGM #2:	1.0361

EMISSION RATES		TUNNEL FLOW RATE:	143.969
Sample Train 1 (g/hr):	0.7216	PARTICULATE CATCH (mg)	
Sample Train 2 (g/hr):	0.7148	Sample Train 1:	1.6
ADJUSTED EMISSION RATES		Sample Train 2:	1.6

Sample Train 1 (g/hr):	1.3883
Sample Train 2 (g/hr):	1.3773

DEVIATION:	0.79%
------------	-------

SFBA EPA ADJUSTED EMISSION RESULTS

Manufacturer:	Morso	RESULTS	
Model:	1410		
Date:	02/08/00	AVERAGE ADJUSTED EMISSION R/	4.317
Run:	4		
Project #:	31218	Burn Rate (Dry kg/hr):	1.826
Test Duration: (minutes)	65		

PRESSURE FACTOR:	0.98229	BAROMETRIC PRESSURE	
		Average:	29.39
TEMPERATURE FACTORS		Start:	29.4
DGM #1:	0.98599	End:	29.38
DGM #2:	0.99015		

DRY GAS METER VALUES

VOLUMES SAMPLED		DGM #1	Final:	204.157
	DGM #1:	15.25379	Initial:	188.651
	DGM #2:	15.55224		
		DGM #2	Final:	580.903
TOTAL TUNNEL VOLUME (scf):	9262.571		Initial:	565.470

SAMPLE RATIOS		TEMPERATURES (DEG. RANKIN)	
Sample Train 1:	607.231	DGM #1:	535.500
Sample Train 2:	595.578	DGM #2:	533.250

TOTAL EMISSIONS		CALIBRATION FACTORS	
Sample Train 1 (g):	3.0969	DGM #1:	1.0157
Sample Train 2 (g):	3.0374	DGM #2:	1.0361

EMISSION RATES		TUNNEL FLOW RATE:	142.501
Sample Train 1 (g/hr):	2.8587		
Sample Train 2 (g/hr):	2.8038	PARTICULATE CATCH (mg)	

ADJUSTED EMISSION RATES		Sample Train 1:	5.1
Sample Train 1 (g/hr):	4.3520	Sample Train 2:	5.1
Sample Train 2 (g/hr):	4.2825		

DEVIATION: 1.61%

Manufacturer Morse Model 1410 Date 2-1-00
Job # 31218 Run _____ Tech RA

EMISSIONS TESTING UNIT PREPARATION

Unit description (check all that apply)

- | | | |
|---|--|-------------------------|
| <input checked="" type="checkbox"/> Stove | <input checked="" type="checkbox"/> Top Vent | _____ Manual Draft |
| _____ Insert | _____ Rear Vent | _____ Bimetal Spring |
| _____ Catalytic | <input checked="" type="checkbox"/> Grate | _____ Remote Thermostat |
| <input checked="" type="checkbox"/> Non-catalytic | <input checked="" type="checkbox"/> Ashpan | _____ Blower or Fans |
| Other: _____ | | |

Unit received with all parts: Yes _____ No
Manual: Yes _____ No
Drawings: Yes _____ No
Specifications: Yes _____ No

Materials of construction: CAST IRON

Air introduction: _____
Control mechanism: _____

Unit net weight with all components: _____ lbs. _____ Kg.
Unit fire box volume: 1.736 Ft³ (attach fire box volume calculations and drawings)
Ideal Load Weight: 5.15 lbs. (Volume x 7)
Load Weight Range: ($\pm 10\%$ of ideal weight) 4.64 lbs. to 5.67 lbs.
Ideal piece length specification: 10 inches. (5/6 of longest fire box dimension)
Thermocouples attached: 5 Attached by: RA (attach T/C map)

Unit conditioned prior to test

10 hours at medium burn rate (non-catalytic) (attach burn log)
_____ 50 hours at medium burn rate (attach burn log)

Date started: 1-31-00 Date completed: 2-1-00
Catalyst manufacturer: _____
Serial number: _____ Dimensions: _____ Cell size: _____ cells/in.²
Unit ready for testing (date): _____ Initialed: _____


Manufacturer MORSD Model 1410 Date 2-1-00

Job # 31218 Run _____ Tech RA

Measurements By: RA

Checked By: _____

FIRE BOX VOLUME CALCULATION



Firebox width = 12 Inches

Volume = A+B+C+D+E+F+G

A = 12.5*12*5.625 = 843.75

B = 11.5*1.1272*12 = 155.55

C = 1.9646*6.6550*12 = 156.899

D = .5(6.655*1.7832*12) = 71.20

E = .5(4.125*1.1053*12) = 27.36

F = .5(1*.2679*12) = 1.61

G = .72*1.7832*12 = 15.40

Volume = 1271.769 cubic inches or .736 cubic feet

Manufacturer MORSO Model 1410 Date 2-1-00
Job # 31218 Run _____ Tech RA

Thermocouple Location

THEROCOUPLES WERE PLACED CENTRALLY ON THE LOCATION LISTED BELOW.

TC#	LOCATION
5	UNIT TOP
6	UNIT BACK
7	UNIT RIGHT
8	UNIT LEFT
9	UNIT BOTTOM

Manufacturer MORSO Model 1410 Date 2-3-00
 Job # 31218 Run 1 Tech RA

PRETEST DILUTION TUNNEL TRAVERSE RUN

Barometric pressure (P_{bar}) 28.75 (inches Hg.) Static pressure (P_g) .125 (inches w.c.)
 Inside diameter: Port A 6in. Port B 6in. Tunnel cross sectional area: 0.1963Fi^2
 Pitot tube type: Standard

Traverse Point	Position (inches)	Velocity Head Δ_p (inches H ₂ O)	Tunnel Temperature (°F)	$\sqrt{\Delta_p}$
A-Centroid	3.00	.040	85	.2000
B-Centroid	3.00	.040	84	.2000
A-1	0.40	.037	85	.1920
A-2	1.50	.040	85	.2000
A-3	4.50	.040	85	.2000
A-4	5.60	.036	85	.1897
B-1	0.40	.036	84	.1897
B-2	1.50	.040	84	.2000
B-3	4.50	.040	84	.2000
B-4	5.60	.035	84	.1871
		AVERAGE	84.5	.1959

Adjustment factor application

$$V_s = K_p C_p F_p (\sqrt{\Delta_p})_{AVG} \sqrt{\frac{T_s}{P_s M_s}} \quad V_s = K_p C_p (\sqrt{\Delta_p})_{avg} \sqrt{\frac{T_s}{P_s M_s}}$$

Pitot correction .9795

Where:

- C_p = Pitot tube coefficient = 0.99 for standard pitot
- Δ_p = manometer reading (inches H₂O)
- T_s = average absolute dilution tunnel temperature (°F + 460)
- P_s = absolute dilution tunnel gas pressure or $P_{bar} - P_g$

$$F_p = \frac{(\sqrt{\Delta_p})_{avg}}{(\sqrt{\Delta_p})_{centroid}}$$

P_g = static pressure inches H₂O

M_s = 28.56, wet molecular weight of stack gas (alternatively, it may be measured)
 K_p = 85.49 Pitot tube constant. (conversion factor for English units)

Adjustment factor for alternative Pitot tube placement:

- $(\sqrt{\Delta_p})_{avg}$ = Average of the square roots of the velocity heads (Δ_p) measured at each traverse point.
- $(\sqrt{\Delta_p})_{centroid}$ = Average of the square roots of the velocity heads measured at the tunnel centroid (inches of H₂O)

Manufacturer MORSO Model 1410 Date 23-00
 Job # 31218 Run 1 Tech RA

Pre/Post Checks

Moisture Meter Calibration Check:

Time: <u>8:00</u>	X: <input checked="" type="checkbox"/>	Y: <input checked="" type="checkbox"/>	12: <input checked="" type="checkbox"/>	22: <input checked="" type="checkbox"/>
-------------------	--	--	---	---

Facility Conditions:

	Pre-Test	Post-Test
Air Velocity.....	<u>0</u> fpm	fpm
Smoke Capture Check.....	<input checked="" type="checkbox"/>	

Wood Heater Conditions:

Date Wood Heater Stack Cleaned.....	<u>2-2-00</u>	
Date Dilution Tunnel Cleaned.....	<u>2-2-00</u>	
Induced Draft Check.....	<u>0</u>	
Tunnel Velocity.....	<u>0.40</u>	
Flow Rate 140-cfm ±10%.....		<u>142,931</u>

Pitot Leak Check:

Side A.....		
Side B.....		

Temperature System:

Ambient (65°- 90°F).....		°F
Wood Heater Surface (±125°F).....		°F

Proportional Checks:

CO Analyzer Drift Check.....		
CO ₂ Analyzer Check.....		
O ₂ Analyzer Check.....		
Thermocouple check.....		

Sampling Train ID Numbers:

	Train 1	Train 2
Probe.....	<u>3</u>	<u>4</u>
Filter Front.....	<u>25</u>	<u>27</u>
Filter Back.....	<u>26</u>	<u>28</u>
Filter Thermocouple.....	19	22
Filter 5G-3 (<90°F).....		

Thermocouple Identification Number

Flue.....1	Room.....2	Dilution Tunnel Dry Bulb.....3
Dilution Tunnel Wet Bulb.....4	Unit Top.....5	Unit Back.....6
Unit Right Side.....7	Unit Left Side.....8	Unit Bottom.....9
Catalyst/Combustion Chamber.....10		

Manufacturer MORSO Model 1410 Date 2-3-00
 Job # 31218 Run 1 Tech RA

Pre-Test Scale Audit

Scale Type	Audit Weight	Measured Weight
Platform	<u>10</u> lbs., Class F	<u>10.0</u> lbs.
Wood	<u>10</u> lbs., Class F	<u>10.0</u> lbs.
Analytical	100 Grams <u>100</u> mg, Class S	<u>100</u> Grams <u>100</u> mg.

LIMITS OF WEIGHT RANGES

ANALYTICAL SCALE: 50%-150% of dry filter weight, ± 0.1 mg
PLATFORM SCALE: 20%-80% of ideal test load weight, ± 0.1 lbs. or 1%
WOOD SCALE: 20%-80% of ideal test load weight, ± 0.1 lbs. or 1%

Manufacturer MORSE Model 1410 Date 2.3.08
 Job # 31214 Run 1 Tech RA

SAMPLING EQUIPMENT CHECK OUT

Leakage Checks Tunnel Samplers

	SYSTEM 1		SYSTEM 2	
	Pre-Test	Post-Test	Pre-Test	Post-Test
Unplugged Flow Rate = .25cfm				
Vacuum (inches Hg.)	10 ["]	10 ["]	10 ["]	10 ["]
Final 1minute DGM (ft ³)	106.467	140.768	484.106	518.222
Initial 1minute DGM (ft ³)	106.465	140.765	484.104	518.221
Change (C) (ft ³)	.002		.002	
Allowable leakage .04 x Sample rate or .02cfm	0.0100	0.0100	0.0100	0.0100
Check OK	✓		✓	

Leakage Checks Flue Gas Sampler

	Pre Test	Post Test
Plugged Probe		
Vacuum (inches Hg.)	10 ["]	10
Rotometer Reading (mm)	0	0
Flow Rate (CFM)	0	0
Allowable (.04 x Sample Rate)		
Check OK	✓	✓

Manufacturer MORSO Model 1410 Date 2-3-00
 Job # 31218 Run 1 Tech RA

CONTINUOUS ANALYZERS

Pre-Test (Adjust and Record)

	ZERO		SPAN		CAL. (Record Only)	
CO	<u>0</u>	<u>0</u>	<u>9.99</u>	<u>9.99</u>	<u>.96</u>	<u>.991</u>
CO ₂	<u>0</u>	<u>0</u>	<u>24.65</u>	<u>24.65</u>	<u>9.65</u>	<u>10.02</u>
O ₂	<u>0</u>	<u>0</u>	<u>20.93</u>	<u>20.93</u>	<u>10.14</u>	<u>10.01</u>
	Actual	Should Be	Actual	Should Be	Actual	Should Be

Post Test (Record Only)

	Zero	Span	Cal.	Zero Drift	Span Drift	Cal. Drift	OK?	Not OK*
CO	<u>0</u>	<u>10.01</u>	<u>.96</u>	<u>0</u>	<u>.02</u>	<u>0</u>	<u>/</u>	
CO ₂	<u>.01</u>	<u>24.68</u>	<u>9.65</u>	<u>.01</u>	<u>.03</u>	<u>0</u>	<u>/</u>	
O ₂	<u>.03</u>	<u>20.83</u>	<u>10.16</u>	<u>.03</u>	<u>.10</u>	<u>.02</u>	<u>/</u>	

* Greater than ± 5% of the range used.

Manufacturer Moroso Model 1410 Date 2-3-00
 Job # 31218 Run 1 Tech RA

DILUTION TUNNEL PARTICULATE SAMPLER DATA

FILTER TYPE: Gelman 47mm A/E

Samples in Desecrator. Date: 2-3-00 Time: 14:00

	SYSTEM 1		SYSTEM 2	
	Probe and Front Half Housing #	Filter Numbers	Probe and Front Half Housing #	Filter Numbers
Post Test Weight:	<u>93.1198</u> grams	<u>.2568</u> grams	<u>89.9725</u> grams	<u>.2571</u> grams
Pre Test Weight:	<u>93.1188</u> grams	<u>.2395</u> grams	<u>89.9725</u> grams	<u>.2396</u> Grams
Gain:	<u>0</u> grams	<u>.0173</u> grams	<u>0</u> grams	<u>.0175</u> Grams
	a1	b1	a2	b2

Total Gain: a1 - b1 = .0173 grams a2 - b2 = .0175 grams

		SYSTEM 1			SYSTEM 2			TEMP	HUMID
Pre-test Weight Record	Probe & Housing Number	Front Filter Number	Back Filter Number	Probe & Housing Number	Front Filter Number	Back Filter Number			
Date	Time	<u>3</u>	<u>25</u>	<u>26</u>	<u>4</u>	<u>27</u>	<u>28</u>	°F	%
<u>2-2-00</u>	<u>7:40</u>	<u>93.1195</u>	<u>.1197</u>	<u>.1203</u>	<u>89.9722</u>	<u>.1200</u>	<u>.1201</u>	<u>66</u>	<u>24</u>
<u>2-3-00</u>	<u>7:00</u>	<u>93.1198</u>	<u>.1196</u>	<u>.1199</u>	<u>89.9725</u>	<u>.1196</u>	<u>.1200</u>	<u>65</u>	<u>26</u>
		Total	<u>.2395</u>		Total	<u>.2396</u>			

		SYSTEM 1		SYSTEM 2		TEMP	HUMID
Pre-test Weight Record	Probe & Housing Number	Combined Filter Weight	Number	Probe & Housing Number	Combined Filter Weight		
Date	Time	<u>3</u>		<u>4</u>		°F	%
<u>2-3-00</u>	<u>14:00</u>	<u>93.1225</u>	<u>.2590</u>	<u>89.9752</u>	<u>.2590</u>	<u>78</u>	<u>26</u>
<u>2-4-00</u>	<u>7:05</u>	<u>93.1204</u>	<u>.2569</u>	<u>89.9725</u>	<u>.2571</u>	<u>65</u>	<u>26</u>
<u>2-7-00</u>	<u>7:00</u>	<u>93.1198</u>	<u>.2568</u>	<u>89.9725</u>	<u>.2571</u>	<u>65</u>	<u>25</u>

Manufacturer MORSO Model 1410 Date 2-3-00
 Job # 31218 Run 1 Tech RA

TEST DATA LOG

RAW DRY GAS METER READINGS

	System 1	System 2
Final (ft ³)	140.757	518.210
Initial (ft ³)	106.467	484.106

AMBIENT CONDITIONS

	Start	End
Barometer. (inches Hg)	29.73	28.78
Wet Bulb (°F)	56	59
Dry Bulb (°F)	73	78
Humidity (%)	33	34

Manufacturer MORSO Model 1410 Date 2-3-00

Job # 31218 Run 1 Tech RA

AIR CLOSED TO 1 TURN OPEN

SWITCH NUMBER			1	2	3	4	5	6	7	8	9	10				
READING #	REAL TIME	ELAPSED TIME	WEIGHT REMAINING	FLUE GAS TEMP	ROOM TEMP	TUNNEL DRY BULB	TUNNEL WET BULB	UNIT TOP	UNIT BACK	UNIT NIGHT SIDE	UNIT LEFT SIDE	UNIT BOTTOM	CATALYST DOWNSTREAM	TUNNEL VELOCITY	DRAFT	SMOKE
0	9:56	0	470	336	71	93	69	596	601	391	412	460	786	035	063	H
1		10	400	307	71	88	69	607	577	380	406	484	914	041	061	M
2		20	340	215	72	84	70	589	580	374	396	482	862	040	051	H
3		30	270	310	72	87	70	647	560	368	391	467	1310	039	060	T
4		40	200	249	73	84	70	672	538	398	428	455	1147		053	C
5		50	170	253	73	85	71	594	542	404	430	433	1121	039	051	C
6		60	140	248	73	84	70	556	600	401	429	430	801	040	049	C
7		70	120	225	73	83	71	495	618	393	426	439	712	040	046	C
8		80														
9		90														
10		100														
11		110														
12		120														
13		130														
14		140														
15		150														
16		160														
17		170														
18		180														
19		190														
20		200														
21		210														
22		220														
23		230														
24		240														
25		250														

Comments: 10:30 FIRE STARTED 11:12 FIRE STARTED DOOR OPEN (M.I.V)
10:42 FIRE STARTED

WHI LTO#: 21218 AIR CLOSED TO 1 TURN OPEN
 MANUFACTURER: MIDR-50 MODEL: 15120 FIRE SIZE: LOW
 SWITCH NUMBER: DATE: 2-27-00 RUN#: 1
 page 15 of 46 TECHNICIAN: RA

READING#	REAL TIME	ELAPSED TIME	WEIGHT REMAIN.	CO ₂	CO	FLUE GAS TEMP	ROOM TEMP	TUNNEL TEMP	TUNNEL WET BULB	UNIT TOP	UNIT BACK	UNIT RT. SIDE	UNIT LT. SIDE	UNIT BOTTOM	CAT. EXIT	CAT. CENTER	GAS SMPL. ROTO.	DGM #1 READING	ROTO 1 READING	DGM TEMP INLET	DGM TEMP OUTLET	FILTER TEMP	DGM #2 READING	ROTO 2 READING	DGM TEMP INLET	DGM TEMP OUTLET	DRIFT	SMOKE	MAX DGM PRESS	TUNNEL VELOCITY	TECHNICIAN					
0	1:14	0	5.10	1.75	2.81	11.57	224	73	83	71	491	612	387	423	482	697		135	106.4	77	77	74	784.1	120	74	74	74	040	045	RA						
1		10	4.20	1.41	4.89	10.24	257	74	86	70	510	594	386	409	448	697		135	108.8	77	78	79	486.4	120	75	74	79	040	056	RA						
2		20	3.50	1.26	6.38	6.38	257	75	85	70	525	569	384	394	473	1055		135	111.2	78	78	79	499.8	120	76	75	79	040	087	RA						
3		30	2.70	1.38	16.18	3.84	288	75	85	71	441	526	396	394	480	1275		135	113.6	79	78	79	491.2	120	77	76	80	041	080	RA						
4		40	1.90	1.63	18.36	1.53	305	75	86	71	287	511	416	414	462	1280		135	116.0	79	79	80	493.6	120	77	76	80	041	062	RA						
5		50	1.10	1.43	16.95	2.75	288	76	87	71	764	543	444	440	443	1289		135	118.4	80	79	80	496.0	120	78	77	81	041	061	RA						
6		60	70	4.9	12.52	7.0	230	76	85	71	668	570	441	456	437	954		135	120.8	80	80	80	498.3	120	79	78	80	040	050	RA						
7		70	160	1.75	9.0	10.12	187	75	82	72	552	570	419	444	419	730		135	123.2	81	80	80	500.7	120	80	79	80	041	042	RA						
8		80	320	2.40	6.90	11.60	167	74	81	72	465	545	391	418	407	656		135	125.6	81	81	80	503.1	120	80	80	80	041	039	RA						
9		90	100	1.30	2.78	7.40	10.85	75	81	72	416	530	366	395	396	594		135	128.0	81	81	80	505.5	120	81	80	80	041	035	RA						
10		100	100	2.78	7.40	10.85	147	75	80	72	389	516	347	375	388	560		135	130.4	81	81	80	507.8	120	81	81	80	041	032	RA						
11		110	20	2.78	7.40	10.85	140	75	79	72	367	501	332	359	387	511		135	132.8	82	81	80	510.3	120	81	81	80	040	030	RA						
12		120	26	2.73	6.93	11.57	135	75	79	72	354	486	321	347	371	513		135	135.2	82	81	79	512.6	120	81	81	79	040	029	RA						
13		130	10	1.85	4.06	15.03	147	75	79	71	345	488	320	337	348	502		135	137.6	82	81	79	515.0	120	81	81	79	040	028	RA						
14		140	10	2.11	7.12	11.81	124	74	77	71	340	478	299	329	339	503		135	140.0	82	81	79	517.4	120	81	81	82	040	027	RA						
15		150	0	2.10	6.82	12.8	128	74	77	71	335	472	298	325	352	492		135	140.7	82	82	78	518.2	120	81	81	82	040	026	RA						
16		160																																		
17		170																																		
18		180																																		
19		190																																		
20		200																																		
21		210																																		
22		220																																		
23		230																																		
24		240																																		
25		250																																		
26		260																																		
27		270																																		
28		280																																		
29		290																																		
30		300																																		
31		310																																		
32		320																																		
33		330																																		
34		340																																		
35		350																																		
36		360																																		
37		370																																		
38		380																																		
39		390																																		
40		400																																		
41		410																																		
42		420																																		
43		430																																		
44		440																																		
45		450																																		
46		460																																		
47		470																																		
48		480																																		

RA 13:22
 RA 13:22

COMMENTS: TEST LOADED IN 35 SECONDS DOOR OPEN 3 MIN AIR CONTROL SET AT 13:22 FIRE STIRRED DOOR OPEN 15 SEC SEE SET 643
 RA
 643

3 RA

Manufacturer MONSO Model 1410 Date 2-4-80
 Job # 31218 Run 2 Tech RA

PRETEST DILUTION TUNNEL TRAVERSE RUN

Barometric pressure (P_{bar}) 29.22 (inches Hg.) Static pressure (P_g) 12.8 (inches w.c.)
 Inside diameter: Port A 6in. Port B 6in. Tunnel cross sectional area: $0.1963Ft^2$
 Pitot tube type: Standard

Traverse Point	Position (inches)	Velocity Head Δ_p (inches H ₂ O)	Tunnel Temperature (°F)	$\sqrt{\Delta_p}$
A-Centroid	3.00	.041	86	.2025
B-Centroid	3.00	.041	87	.2025
A-1	0.40	.038	86	.1949
A-2	1.50	.041	86	.2025
A-3	4.50	.039	86	.1975
A-4	5.60	.038	86	.1949
B-1	0.40	.038 0.041	87	.1949
B-2	1.50	.041	87	.2025
B-3	4.50	.041	87	.2025
B-4	5.60	.038	87	.1949
AVERAGE			86.5	.1990

Adjustment factor application

$$V_s = K_p C_p F_p (\sqrt{\Delta_p})_{AVG} \sqrt{\frac{T_s}{P_s M_s}} \quad V_s = K_p C_p (\sqrt{\Delta_p})_{avg} \sqrt{\frac{T_s}{P_s M_s}}$$

Pitot correction .19826

Where:

- C_p = Pitot tube coefficient = 0.99 for standard pitot
- Δ_p = manometer reading (inches H₂O)
- T_s = average absolute dilution tunnel temperature (°F - 460)
- P_s = absolute dilution tunnel gas pressure or $P_{bar} + P_g$

$$F_p = \frac{(\sqrt{\Delta_p})_{avg}}{(\sqrt{\Delta_p})_{centroid}}$$

P_s = static pressure inches H₂O
13.6

M_s = 28.56, wet molecular weight of stack gas (alternatively, it may be measured)
 K_p = 85.49 Pitot tube constant. (conversion factor for English units)

Adjustment factor for alternative Pitot tube placement:

- $(\sqrt{\Delta_p})_{avg}$ = Average of the square roots of the velocity heads (Δ_p) measured at each traverse point.
- $(\sqrt{\Delta_p})_{centroid}$ = Average of the square roots of the velocity heads measured at the tunnel centroid (inches of H₂O)

Manufacturer MORSO Model 1410 Date 2-4-00
 Job # 31218 Run 2 Tech RA

Pre/Post Checks

Moisture Meter Calibration Check:

Time: <u>9:00</u>	X: <input checked="" type="checkbox"/>	Y: <input type="checkbox"/>	12: <input type="checkbox"/>	22: <input checked="" type="checkbox"/>
-------------------	--	-----------------------------	------------------------------	---

Facility Conditions:

Air Velocity.....
 Smoke Capture Check.....

Pre-Test	Post-Test
0 fpm	0 fpm
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>

Wood Heater Conditions:

Date Wood Heater Stack Cleaned.....
 Date Dilution Tunnel Cleaned.....
 Induced Draft Check.....
 Tunnel Velocity.....
 Flow Rate 140-cfm ±10%.....

<u>2-2-00</u>	
<u>2-2-00</u>	
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
<u>.039</u>	
	<u>143.895</u>

Pitot Leak Check:

Side A.....
 Side B.....

<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>

Temperature System:

Ambient (65°- 90°F).....
 Wood Heater Surface (±125°F).....

	°F
<u>-65.4</u>	°F

Proportional Checks:

CO Analyzer Drift Check.....
 CO₂ Analyzer Check.....
 O₂ Analyzer Check.....
 Thermocouple check.....

<input checked="" type="checkbox"/>
<input checked="" type="checkbox"/>
<input checked="" type="checkbox"/>
<input checked="" type="checkbox"/>

Sampling Train ID Numbers:

Probe.....
 Filter Front.....
 Filter Back.....
 Filter Thermocouple.....
 Filter SG-3 (<90°F).....

Train 1	Train 2
19	22

Thermocouple Identification Number

Flue.....1
 Dilution Tunnel Wet Bulb.....4
 Unit Right Side.....7
 Catalyst/Combustion Chamber.....10

Room.....2
 Unit Top.....5
 Unit Left Side.....8

Dilution Tunnel Dry Pipe.....3
 Unit Back.....6
 Unit Bottom.....9

Manufacturer MORSO Model 1410 Date 2-4-00
 Job # 31218 Run 2 Tech RA

Pre-Test Scale Audit

Scale Type	Audit Weight	Measured Weight
Platform	<u>10</u> lbs., Class F	<u>10.0</u> lbs.
Wood	<u>10</u> lbs., Class F	<u>10.00</u> lbs.
Analytical	100 Grams <u>100</u> mg, Class S	<u>100</u> Grams <u>100</u> mg.

LIMITS OF WEIGHT RANGES

ANALYTICAL SCALE: 50%-150% of dry filter weight, \pm 0.1 mg
PLATFORM SCALE: 20%-80% of ideal test load weight, = 0.1 lbs. or 1%
WOOD SCALE: 20%-80% of ideal test load weight, = 0.1 lbs. or 1%

Manufacturer MORSE Model 1410 Date 2-4-00
 Job # 31218 Run 2 Tech RA

SAMPLING EQUIPMENT CHECK OUT

Leakage Checks Tunnel Samplers

	SYSTEM 1		SYSTEM 2	
	Pre-Test	Post-Test	Pre-Test	Post-Test
Unplugged Flow Rate = .25cfm				
Vacuum (inches Hg.)	10"	10"	10"	10"
Final 1minute DGM (ft ³)	140.773	168.980	518.222	546.072
Initial 1minute DGM (ft ³)	140.772	168.979	518.225	546.072
Change (C) (ft ³)	.001	.001	.001	
Allowable leakage .04 x Sample rate or .02cfm	0.0100	0.0100	0.0100	0.0100
Check OK	✓	✓	✓	✓

Leakage Checks Flue Gas Sampler

	Pre Test	Post Test
Plugged Probe		
Vacuum (inches Hg.)	10"	10"
Rotometer Reading (mm)	0	0
Flow Rate (CFM)	0	0
Allowable (.04 x Sample Rate)		
Check OK	✓	✓

Manufacturer MORSO Model 1410 Date 2-4-00
 Job # 31218 Run 2 Tech RA

CONTINUOUS ANALYZERS

Pre-Test (Adjust and Record)

	ZERO		SPAN		CAL. (Record Only)	
CO	D	D	9.99	9.99	.97	.991
CO ₂	D	D	24.65	24.65	9.71	10.02
O ₂	D	D	20.93	20.93	10.09	10.01
	Actual	Should Be	Actual	Should Be	Actual	Should Be

Post Test (Record Only)

	Zero	Span	Cal.	Zero Drift	Span Drift	Cal. Drift	OK?	Not OK*
CO	D	10.04	.98	0	.05	.01	/	
CO ₂	02	24.75	9.85	.02	.30	.14	/	
O ₂	104	20.83	10.12	.04	.10	.03	/	

* Greater than ± 5% of the range used.

Manufacturer MORSO Model 1410 Date 2-4-08

Job # 31218 Run 2 Tech RA

TEST DATA LOG

RAW DRY GAS METER READINGS

	System 1	System 2
Final (ft ³)	168,970	546.063
Initial (ft ³)	140.773	518.222

AMBIENT CONDITIONS

	Start	End
Barometer. (inches Hg)	29.22	29.28
Wet Bulb (°F)	56	58
Dry Bulb (°F)	72	78
Humidity (%)	35	28



Manufacturer MORSO Model 1470 Date 2-4-00

Job # 31218 Run 2 Tech RA

AIR CONTROL 1 1/4 TURNS FROM CLOSED

SWITCH NUMBER			1	2	3	4	5	6	7	8	9	10				
READING #	REAL TIME	ELAPSED TIME	WEIGHT REMAINING	FLUE GAS TEMP	ROOM TEMP	TUNNEL DRY BULB	TUNNEL WET BULB	UNIT TOP	UNIT BACK	UNIT RIGHT SIDE	UNIT LEFT SIDE	UNIT BOTTOM	CATALYST DOWNSTREAM	TUNNEL VELOCITY	DRAFT	SMOKE
0	9:37	0	4.90	501	71	118	64	714	746	444	478	557	1165	040	078	C
1		10	4.10	311	70	88	65	700	633	441	480	529	1110	045	068	C
2		20	3.30	303	71	86	66	751	593	436	483	510	1268	040	065	C
2.350		30	2.50	290	72	86	67	761	579	438	486	476	1294		062	C
4		40	1.90	268	73	85	67	748	576	449	490	450	1076	040	057	C
5		50	1.60	236	72	83	68	646	581	434	474	435	993	039	056	C
6		60	1.40	207	73	81	68	543	612	414	456	430	720	039	045	C
7		70	1.20	186	73	79	68	470	611	388	430	431	672	039	040	C
8		80														
9		90														
10		100														
11		110														
12		120														
13		130														
14		140														
15		150														
16		160														
17		170														
18		180														
19		190														
20		200														
21		210														
22		220														
23		230														
24		240														
25		250														

Comments:

10:30 FIRE STARTED 10:54 FIRE STARTED DOOR OPEN 55902

WHI LTO#: 31218 MANUFACTURER: MOR-50 SWITCH NUMBER: 1410 AIR CONTROL 1/4 TURN FROM CLOSED DATE: 2-4-00 RUN#: 2 TECHNICIAN: RM

READING	REAL TIME	WEIGHT REMAIN	CO ₂	CO	O ₂	FLUE GAS TEMP	ROOM TEMP	TUNNEL TEMP	TUNNEL WET BULB	UNIT TOP	UNIT BACK	UNIT RT. SIDE	UNIT LEFT SIDE	UNIT BOTTOM	CAT INLET	CAT CENTER	GAS SMPL. ROTO.	DCM #1 READING	ROTO 1 READING	DCM TEMP INLET	DCM TEMP OUTLET	FILTER TEMP	DCM #2 READING	ROTO 2 READING	DCM TEMP INLET	DCM TEMP OUTLET	FILTER TEMP	TUNNEL VELOCITY	INHAFT	SMOKE	MAX DGM PRESS			
0	0:56	0	1.40	8.63	10.80	280	83	73	69	409	600	319	409	448	552		135	140.773	120	77	76	74	518	120	74	74	74	1029	040	C	22			
1		3.80	1.58	4.91	4.48	335	74	93	69	468	666	397	429	518	1073		135	143.1	120	77	77	81	520.5	120	74	73	80	1039	070	7	2			
2		2.00	1.36	8.66	2.08	307	74	88	69	787	623	411	453	509	1158		135	145.5	120	77	77	80	522.9	120	75	74	80	1029	048	C	2			
3		3.00	85	8.48	1.91	296	74	87	70	770	606	474	463	486	1227		135	147.9	120	79	78	80	525.3	120	77	75	80	1041	065	C	2			
4		1.30	1.53	18.75	1.11	289	75	87	70	808	594	441	471	464	1275		135	150.3	120	79	78	80	527.7	120	77	76	80	1041	041	C	2			
5		1.70	3.6	13.89	1.69	255	76	85	70	741	597	452	480	443	998		135	152.7	120	79	78	80	530.1	120	79	78	80	1040	084	C	2			
6		1.50	2.24	8.74	10.15	214	76	83	70	590	598	484	465	432	762		135	155.1	120	79	78	80	532.5	120	79	79	80	1040	047	C	2			
7		1.50	2.55	8.56	10.12	191	75	81	70	494	588	485	437	426	714		135	157.5	120	79	79	80	534.8	120	79	79	79	1040	043	C	2			
8		1.40	2.46	7.76	10.83	171	74	80	70	455	581	382	415	422	667		135	160.8	120	80	80	80	537.2	120	79	79	79	1040	040	C	2			
9		1.30	2.58	2.72	10.97	148	74	79	70	423	569	365	398	415	645		135	162.4	120	80	80	77	539.6	120	77	77	79	1040	038	C	2			
10		1.20	2.48	1.20	11.64	160	74	79	70	399	556	351	383	406	598		135	164.8	120	80	80	79	542.0	120	80	80	79	1040	035	C	2			
11		1.10	2.32	1.69	12.24	155	75	78	70	387	535	341	369	395	574		135	167.2	120	80	80	79	544.3	120	80	80	79	1040	035	C	2			
12	1:17	1.00	2.29	1.47	12.46	151	74	78	70	369	522	334	359	386	558		135	168.7	120	80	80	79	546.0	120	80	80	78	1039	034	C	2			
13		1.40																																
14		1.50																																
15		1.60																																
16		1.70																																
17		1.80																																
18		1.90																																
19		2.00																																
20		2.10																																
21		2.20																																
22		2.30																																
23		2.40																																
24		2.50																																
25		2.60																																
26		2.70																																
27		2.80																																
28		2.90																																
29		3.00																																
30		3.10																																
31		3.20																																
32		3.30																																
33		3.40																																
34		3.50																																
35		3.60																																
36		3.70																																
37		3.80																																
38		3.90																																
39		4.00																																
40		4.10																																
41		4.20																																
42		4.30																																
43		4.40																																
44		4.50																																
45		4.60																																
46		4.70																																
47		4.80																																
48																																		

456 Kg/hr

117 min

COMMENTS: TEST LOADED IN 25 SECONDS DOOR CLOSED AT 5 min. AIR CONTROL NOT ADJUSTED

Manufacturer MORSO Model 1410 Date 2-7-00
 Job # 31218 Run 3 Tech RA

PRETEST DILUTION TUNNEL TRAVERSE RUN

Barometric pressure (P_{bar}) 29.34 (inches Hg.) Static pressure (P_q) .128 (inches w.c.)
 Inside diameter: Port A 6in. Port B 6in. Tunnel cross sectional area: 0.1963Ft²
 Pitot tube type: Standard

Traverse Point	Position (inches)	Velocity Head Δ_p (inches H ₂ O)	Tunnel Temperature (°F)	$\sqrt{\Delta_p}$	
A-Centroid	3.00	.040	103	.2000	
B-Centroid	3.00	.039	99	.1975	
A-1	0.40	.036	102	.1897	
A-2	1.50	.041	102	.2025	
A-3	4.50	.040	103	.2000	
A-4	5.60	.037	102	.1924	
B-1	0.40	.036	101	.1897	
B-2	1.50	.040	100	.2000	
B-3	4.50	.040	99	.2000	
B-4	5.60	.035	101	.1871	
AVERAGE				101.2	.1959

Adjustment factor application

$$V_s = K_p C_p F_p (\sqrt{\Delta_p})_{AVG} \sqrt{\frac{T_s}{P_s M_s}} \quad V_s = K_p C_p (\sqrt{\Delta_p})_{avg} \sqrt{\frac{T_s}{P_s M_s}}$$

Pitot correction .9856

Where:
 C_p = Pitot tube coefficient = 0.99 for standard pitot
 Δ_p = manometer reading (inches H₂O)
 T_s = average absolute dilution tunnel temperature (°F + 460)
 P_s = absolute dilution tunnel gas pressure or $P_{bar} - P_q$

$$F_p = \frac{(\sqrt{\Delta_p})_{avg}}{(\sqrt{\Delta_p})_{centroid}}$$

P_q = static pressure inches H₂O

M_s = 28.56 wet molecular weight of stack gas (alternatively, it may be measured)
 K_p = 85.49 Pitot tube constant. (conversion factor for English units)

Adjustment factor for alternative Pitot tube placement:

$(\sqrt{\Delta_p})_{avg}$ = Average of the square roots of the velocity heads (Δ_p) measured at each traverse point.
 $(\sqrt{\Delta_p})_{centroid}$ = Average of the square roots of the velocity heads measured at the tunnel centroid (inches of H₂O)

Manufacturer MORSD Model 1410 Date 2-7-00
 Job # 31218 Run 3 Tech RA

Pre/Post Checks

Moisture Meter Calibration Check:

Time: <u>8:15</u>	X: <input checked="" type="checkbox"/>	Y: <input checked="" type="checkbox"/>	12: <input checked="" type="checkbox"/>	22: <input checked="" type="checkbox"/>
-------------------	--	--	---	---

Facility Conditions:

Air Velocity.....
 Smoke Capture Check.....

Pre-Test	Post-Test
<u>0</u> fpm	<u>0</u> fpm
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>

Wood Heater Conditions:

Date Wood Heater Stack Cleaned.....
 Date Dilution Tunnel Cleaned.....
 Induced Draft Check.....
 Tunnel Velocity.....
 Flow Rate 140-cfm ±10%.....

<u>2-2-00</u>	
<u>2-2-00</u>	
<u>0</u>	<u>0</u>
<u>.039</u>	
	<u>143,969</u>

Pitot Leak Check:

Side A.....
 Side B.....

<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>

Temperature System:

Ambient (65°- 90°F).....
 Wood Heater Surface (±125°F).....

<input checked="" type="checkbox"/>	°F
<u>-18.6</u>	°F

Proportional Checks:

CO Analyzer Drift Check.....
 CO₂ Analyzer Check.....
 O₂ Analyzer Check.....
 Thermocouple check.....

<input checked="" type="checkbox"/>	
<input checked="" type="checkbox"/>	
<input checked="" type="checkbox"/>	
<input checked="" type="checkbox"/>	

Sampling Train ID Numbers:

Probe.....
 Filter Front.....
 Filter Back.....
 Filter Thermocouple.....
 Filter 5G-3 (<90°F).....

Train 1	Train 2
<u>7</u>	<u>8</u>
<u>33</u>	<u>35</u>
<u>34</u>	<u>36</u>
<u>19</u>	<u>22</u>
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>

Thermocouple Identification Number

Flue.....1	Room.....2
Dilution Tunnel Wet Bulb.....4	Unit Top.....5
Unit Right Side.....7	Unit Left Side.....8
Catalyst/Combustion Chamber.....10	

Dilution Tunnel Dry Bulb.....3	Unit Back.....6
Unit Bottom.....9	

Manufacturer MORSO Model 1410 Date 2-7-00
 Job # 21218 Run 3 Tech RA

Pre-Test Scale Audit

Scale Type	Audit Weight	Measured Weight
Platform	<u>10</u> lbs., Class F	<u>10.0</u> lbs.
Wood	<u>10</u> lbs., Class F	<u>10.00</u> lbs.
Analytical	100 Grams <u>100</u> mg, Class S	<u>100</u> Grams <u>100</u> mg.

LIMITS OF WEIGHT RANGES

ANALYTICAL SCALE: 50%-150% of dry filter weight, ± 0.1 mg
PLATFORM SCALE: 20%-80% of ideal test load weight, = 0.1 lbs. or 1%
WOOD SCALE: 20%-80% of ideal test load weight, = 0.1 lbs. or 1%

Manufacturer MORSO Model 1410 Date 2-7-00
 Job # 31218 Run 3 Tech RA

SAMPLING EQUIPMENT CHECK OUT

Leakage Checks Tunnel Samplers

	SYSTEM 1		SYSTEM 2	
	Pre-Test	Post-Test	Pre-Test	Post-Test
Unplugged Flow Rate = .25cfm				
Vacuum (inches Hg.)	10"	10"	10"	10"
Final 1minute DGM (ft ³)	168,997	188,644	546,085	565,463
Initial 1minute DGM (ft ³)	1168,995	188,643	546,081	565,460
Change (C) (ft ³)	1,003	1,001	,004	003
Allowable leakage .04 x Sample rate or .02cfm	0.0100	0.0100	0.0100	0.0100
Check OK	✓	✓	✓	✓

Leakage Checks Flue Gas Sampler

	Pre Test	Post Test
Plugged Probe		
Vacuum (inches Hg.)	10"	10"
Rotometer Reading (mm)	0	0
Flow Rate (CFM)	0	0
Allowable (.04 x Sample Rate)		
Check OK	✓	✓

Manufacturer MORSO Model 1410 Date 2-7-00
 Job # 31218 Run 3 Tech RA

CONTINUOUS ANALYZERS

Pre-Test (Adjust and Record)

	ZERO		SPAN		CAL. (Record Only)	
CO	0	0	9.99	9.99	.97	.991
CO ₂	0	0	24.65	24.65	9.72	10.02
O ₂	0	0	20.93	20.93	10.09	10.01
	Actual	Should Be	Actual	Should Be	Actual	Should Be

Post Test (Record Only)

	Zero	Span	Cal.	Zero Drift	Span Drift	Cal. Drift	OK?	Not OK*
CO	0	10.00	.97	0	.01	0	/	
CO ₂	.04	24.78	9.79	.04	.13	.07	/	
O ₂	.06	20.73	10.14	.06	.20	.05	/	

* Greater than ± 5% of the range used.

Manufacturer MORSO Model 1410 Date 2-7-08
 Job # 31218 Run 3 Tech RA

TEST DATA LOG

RAW DRY GAS METER READINGS

	System 1	System 2
Final (ft ³)	188,630	545.450
Initial (ft ³)	168,997	546.085

AMBIENT CONDITIONS

	Start	End
Barometer. (inches Hg)	29.34	29.40
Wet Bulb (°F)	56	59
Dry Bulb (°F)	70	90
Humidity (%)	41	30

Manufacturer MOKSO Model 1410 Date 2-7-00

Job # 31218 Run 3 Tech RA

AIR CONTROL 2 1/2 TURNS FROM CLOSED

SWITCH NUMBER		1	2	3	4	5	6	7	8	9	10					
READING #	REAL TIME	ELAPSED TIME	WEIGHT REMAINING	FLUE GAS TEMP	ROOM TEMP	TUNNEL DRY BULB	TUNNEL WET BULB	UNIT TOP	UNIT BACK	UNIT RIGHT SIDE	UNIT LEFT SIDE	UNIT BOTTOM	CATALYST DOWNSTREAM	TUNNEL VELOCITY	DRAFT	SMOKE
0		0	5.10	460	67	103	69	850	631	450	495	530	1424	0.39	0.82	C
1		10	3.70	457	71	103	70	927	641	466	504	527	1417	0.39	0.81	C
2		20	2.50	431	73	101	71	927	661	502	537	535	1348		0.80	C
3		30	1.80	341	73	94	71	797	662	513	553	544	1055	0.39	0.68	C
4		40	1.60	278	72	89	72	624	646	486	521	548	798	0.38	0.59	C
5		50	1.40	271	71	87	71	540	632	442	475	537	817	0.40	0.56	C
6		60	1.30	267	70	86	71	523	623	416	446	532	802	0.40	0.55	C
7		70	1.10	254	70	84	71	494	605	401	426	526	731	0.38	0.54	C
8		80														
9		90														
10		100														
11		110														
12		120														
13		130														
14		140														
15		150														
16		160														
17		170														
18		180														
19		190														
20		200														
21		210														
22		220														
23		230														
24		240														
25		250														

Comments:

10:35 FIRE STIRRED DOOR OPEN 30SEC

WHI LTO#: 3/2/18 AIR CONT ADC 2 1/2 TURNS FROM CLOSED
 MANUFACTURER: BORSO MODEL: 1410 FIRE SIZE: 2.7.00 DATE: 2.7.00 RUN#: 3 TECHNICIAN: RA
 SWITCH NUMBER: 1034

READING#	REAL TIME	RELEASED TIME	WEIGHT REMAIN.	(%)	(%)	(%)	FLUE GAS TEMP	ROOM TEMP	TUNNEL TEMP	TUNNEL WET BULB	UNIT TOP	UNIT BACK	UNIT RT. SIDE	UNIT LEFT SIDE	UNIT BOTTOM	CAT EXIT	CAT CENTER	11	12	13	GAS SMPL. ROTD.	DGM #1 READING	ROTO 1 READING	DGM1 TEMP INLET	DGM1 TEMP OUTLET	FILTER TEMP	DGM #2 READING	ROTO 2 READING	DGM TEMP INLET	DGM TEMP OUTLET	FILTER TEMP	FUNNEL VELOCITY	DRAFT	SMOKE	MAX DGM PRESS	
0	10:34	0	516	127	6.66	13.19	252	68	85	71	486	605	401	425	525	71	71				135	168997	120	76	76	74	546.085	120	73	73	73	059	072	0		
1		10	370	146	18.55	1.25	438	70	102	73	504	597	413	440	579	1388					135	171.3	120	77	77	83	548.4	120	75	74	83	039	082	2		
2		20	250	146	11.84	2.44	417	72	99	72	878	593	444	470	558	1390					135	173.7	120	78	78	84	552.7	120	76	74	83	041	081	2		
3		30	150	99	17.20	2.39	393	75	97	72	881	620	480	527	544	1370					135	176.1	120	78	78	84	553.1	120	71	75	83	040	075	2		
4		40	90	116	12.59	7.83	357	76	91	73	785	640	497	541	536	1109					135	178.5	120	79	79	84	555.4	120	78	71	84	040	071	2		
5		50	50	80	8.85	11.05	311	76	93	73	644	644	488	520	527	903					135	180.9	120	81	80	84	557.8	120	79	77	84	040	064	2		
6		60	40	153	6.57	13.04	277	75	90	73	559	642	457	489	521	751					135	183.3	120	81	80	84	560.2	120	80	80	84	041	060	2		
7		70	20	227	5.17	14.08	257	75	88	73	498	613	426	457	508	687					135	185.7	120	83	82	83	562.6	120	82	80	83	040	056	2		
8		80	10	228	4.75	14.59	239	75	86	73	454	606	377	429	448	682					135	188.1	120	83	83	82	564.9	120	83	81	82	041	053	2		
9	82	08	D	2.45	4.50	14.23	236	75	86	73	446	605	373	424	481	624					135	188.6	120	83	83	82	565.4	120	82	82	82	041	053	2		
10		100																																		
11		110																																		
12		120																																		
13		130																																		
14		140																																		
15		150																																		
16		160																																		
17		170																																		
18		180																																		
19		190																																		
20		200																																		
21		210																																		
22		220																																		
23		230																																		
24		240																																		
25		250																																		
26		260																																		
27		270																																		
28		280																																		
29		290																																		
30		300																																		
31		310																																		
32		320																																		
33		330																																		
34		340																																		
35		350																																		
36		360																																		
37		370																																		
38		380																																		
39		390																																		
40		400																																		
41		410																																		
42		420																																		
43		430																																		
44		440																																		
45		450																																		
46		460																																		
47		470																																		
48		480																																		

82-1221A
 1.395 kg/HK

COMMENTS: TEST LOADED IN 20 SECONDS DOSE CLOSED AT 5:00 AIR NOT ADJUSTED

Manufacturer MORSO Model 1410 Date 2-8-00
 Job # 31218 Run 4 Tech RA

PRETEST DILUTION TUNNEL TRAVERSE RUN

Barometric pressure (P_{bar}) 29.40 (inches Hg.) Static pressure (P_s) 137 (inches w.c.)
 Inside diameter: Port A 6in. Port B 6in. Tunnel cross sectional area: 0.1963Ft²
 Pitot tube type: Standard

Traverse Point	Position (inches)	Velocity Head Δ_p (inches H ₂ O)	Tunnel Temperature (°F)	√ Δ_p
A-Centroid	3.00	.041	103	.2025
B-Centroid	3.00	.042	100	.2049
A-1	0.40	.038	99	.1949 .1949
A-2	1.50	.042	102	.2049
A-3	4.50	.042	102	.2049
A-4	5.60	.040	101	.2000
B-1	0.40	.038	102	.1949
B-2	1.50	.042	102	.2049
B-3	4.50	.041	101	.2025
B-4	5.60	.038	102	.1949
AVERAGE			101.4	.2010

Adjustment factor application

$$V_s = K_p C_p F_p (\sqrt{\Delta_p})_{AVG} \sqrt{\frac{T_s}{P_s M_s}} \quad V_s = K_p C_p (\sqrt{\Delta_p})_{avg} \sqrt{\frac{T_s}{P_s M_s}}$$

Pitot correction 9865

Where:
 C_p = Pitot tube coefficient = 0.99 for standard pitot
 Δ_p = manometer reading (inches H₂O)
 T_s = average absolute dilution tunnel temperature (°F + 460)
 P_s = absolute dilution tunnel gas pressure or $P_{bar} - P_s$

$$F_p = \frac{(\sqrt{\Delta_p})_{avg}}{(\sqrt{\Delta_p})_{centroid}}$$

P_s = static pressure inches H₂O
 M_s = 28.56, wet molecular weight of stack gas (alternatively, it may be measured)
 K_p = 85.49 Pitot tube constant, (conversion factor for English units)

Adjustment factor for alternative Pitot tube placement:

$(\sqrt{\Delta_p})_{avg}$ = Average of the square roots of the velocity heads (Δ_p) measured at each traverse point.
 $(\sqrt{\Delta_p})_{centroid}$ = Average of the square roots of the velocity heads measured at the tunnel centroid (inches of H₂O)

Manufacturer MORSO Model 1410 Date 2-8-00
 Job # 31218 Run 4 Tech RA

Pre/Post Checks

Moisture Meter Calibration Check:

Time: <u>8:15</u>	X: <input checked="" type="checkbox"/>	Y: <input checked="" type="checkbox"/>	12: <input checked="" type="checkbox"/>	22: <input checked="" type="checkbox"/>
-------------------	--	--	---	---

Facility Conditions:

	Pre-Test	Post-Test
Air Velocity.....	<u>0</u> fpm	<u>0</u> fpm
Smoke Capture Check.....	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>

Wood Heater Conditions:

Date Wood Heater Stack Cleaned.....	<u>2-2-00</u>	
Date Dilution Tunnel Cleaned.....	<u>2-2-00</u>	
Induced Draft Check.....	<u>0</u>	<u>0</u>
Tunnel Velocity.....	<u>1.039</u>	<u>142</u>
Flow Rate 140-cfm ±10%.....		<u>142.501</u>

Pitot Leak Check:

Side A.....	<input checked="" type="checkbox"/>	
Side B.....	<input checked="" type="checkbox"/>	

Temperature System:

Ambient (65°- 90°F).....	<input checked="" type="checkbox"/>	°F
Wood Heater Surface (±125°F).....	<u>+30.8</u>	°F

Proportional Checks:

CO Analyzer Drift Check.....	<input checked="" type="checkbox"/>
CO ₂ Analyzer Check.....	<input checked="" type="checkbox"/>
O ₂ Analyzer Check.....	<input checked="" type="checkbox"/>
Thermocouple check.....	<input checked="" type="checkbox"/>

Sampling Train ID Numbers:

	Train 1	Train 2
Probe.....	<u>9</u>	<u>10</u>
Filter Front.....	<u>37</u>	<u>39</u>
Filter Back.....	<u>38</u>	<u>40</u>
Filter Thermocouple.....	<u>19</u>	<u>22</u>
Filter 5G-3 (<90°F).....	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>

Thermocouple Identification Number

Flue.....1	Room.....2	Dilution Tunnel Dry Bulb.....3
Dilution Tunnel Wet Bulb.....4	Unit Top.....5	Unit Back.....6
Unit Right Side.....7	Unit Left Side.....8	Unit Bottom.....9
Catalyst/Combustion Chamber.....10		

Manufacturer MORSO Model 1410 Date 2-8-00
 Job # 31218 Run 4 Tech RA

Pre-Test Scale Audit

Scale Type	Audit Weight	Measured Weight
Platform	<u>10</u> lbs., Class F	<u>10.0</u> lbs.
Wood	<u>10</u> lbs., Class F	<u>10.00</u> lbs.
Analytical	100 Grams <u>100</u> mg, Class S	<u>100</u> Grams <u>100</u> mg.

LIMITS OF WEIGHT RANGES

ANALYTICAL SCALE 50%-150% of dry filter weight, ± 0.1 mg
PLATFORM SCALE 20%-80% of ideal test load weight, ± 0.1 lbs. or 1%
WOOD SCALE 20%-80% of ideal test load weight, ± 0.1 lbs. or 1%

Manufacturer MORSO Model 1410 Date 2-8-05
 Job # 31218 Run 4 Tech RA

SAMPLING EQUIPMENT CHECK OUT

Leakage Checks Tunnel Samplers

	SYSTEM 1		SYSTEM 2	
	Pre-Test	Post-Test	Pre-Test	Post-Test
Unplugged Flow Rate = .25cfm				
Vacuum (inches Hg.)	10"	10"	10"	10"
Final 1minute DGM (ft ³)	188,651	204,164	565,470	580,920
Initial 1minute DGM (ft ³)	188,650	204,162	565,468	580,916
Change (C) (ft ³)	.001	.002	.002	.004
Allowable leakage .04 x Sample rate or .02cfm	0.0100	0.0100	0.0100	0.0100
Check OK	✓	✓	✓	✓

Leakage Checks Flue Gas Sampler

	Pre Test	Post Test
Plugged Probe		
Vacuum (inches Hg.)	10"	10"
Rotometer Reading (mm)	0	0
Flow Rate (CFM)	0	0
Allowable (.04 x Sample Rate)		
Check OK	✓	✓

Manufacturer MOKSO Model 1410 Date 2-8-00
 Job # 31218 Run 4 Tech RA

CONTINUOUS ANALYZERS

Pre-Test (Adjust and Record)

	ZERO		SPAN		CAL. (Record Only)	
CO	0	0	9.99	9.99	.97	.991
CO ₂	0	0	24.25	24.65	9.71	10.02
O ₂	0	0	20.93	20.93	10.07	10.01
	Actual	Should Be	Actual	Should Be	Actual	Should Be

Post Test (Record Only)

	Zero	Span	Cal.	Zero Drift	Span Drift	Cal. Drift	OK?	Not OK*
CO	0	9.99	.96	0	0	.01	✓	
CO ₂	.02	24.73	9.78	.02	.08	.07	✓	
O ₂	.08	20.61	10.07	.08	.32	0	✓	

* Greater than ± 5% of the range used.

Manufacturer MORSO Model 1410 Date 2-8-08
 Job # 31218 Run 4 Tech RD

TEST DATA LOG

RAW DRY GAS METER READINGS

	System 1	System 2
Final (ft ³)	204.157	580.903
Initial (ft ³)	188.651	565.470

AMBIENT CONDITIONS

	Start	End
Barometer. (inches Hg)	29.40	29.38
Wet Bulb (°F)	52	56
Dry Bulb (°F)	68	76
Humidity (%)	32	25

Manufacturer MORSD Model 1410 Date 2-8-00

Job # 31218 Run 4 Tech RA
AIR CONTROL FULL OPEN 3/4 TURNS

SWITCH NUMBER		1	2	3	4	5	6	7	8	9	10					
READING #	REAL TIME	ELAPSED TIME	WEIGHT REMAINING	FLUE GAS TEMP	ROOM TEMP	TUNNEL DRY BULB	TUNNEL WET BULB	UNIT TOP	UNIT BACK	UNIT RIGHT SIDE	UNIT LEFT SIDE	UNIT BOTTOM	CATALYST DOWNSTREAM	TUNNEL VELOCITY	DRAFT	SMOKE
0	9:06	0	6.10	476	67	112	62	751	630	439	481	410	1316			
1		10	4.50	516	67	103	63	942	580	465	500	423	1422	043	082	C
2		20	3.00	492	72	99	65	939	615	501	528	437	1346		082	C
3		30	1.90	462	71	99	64	932	674	515	559	462	1367	040	082	C
4		40	1.40	318	72	87	65	745	696	506	564	478	967	039	065	C
5		50	1.30	235	70	82	66	593	685	473	525	478	751	038	051	C
6		60	1.20	247	71	80	65	508	679	434	480	477	697	041	052	C
7		70														
8		80														
9		90														
10		100														
11		110														
12		120														
13		130														
14		140														
15		150														
16		160														
17		170														
18		180														
19		190														
20		200														
21		210														
22		220														
23		230														
24		240														
25		250														

Comments:

10:08 FIRE STARTED DOOR OPEN 15 SEC

READING#	REAL TIME	ELAPSED TIME	W/BIGHT REMAIN.	C3	C2	O2	FLUE GAS TEMP	ROOM TEMP	TUNNEL TEMP	TUNNEL WET BULB	UNIT TEMP	UNIT BACK	UNIT RT. SIDE	UNIT LEFT SIDE	UNIT BOTTOM	CAT UNIT	CAT CENTER	GAS SMPL. ROTO.	DGM #1 READING	ROTO 1 READING	DGM TEMP INLET	DGM TEMP OUTLET	19	DGM #2 READING	ROTO 2 READING	DGM TEMP INLET	DGM TEMP ORIFICE	FILTER TEMP	TUNNEL VELOCITY	DRAFT	SMOKE	MAX DGM PRESS	
0	10:09	0	536	204	607	12.99	244	71	80	65	525	678	481	477	477	683		135	188.6	120	72	72	70	516.54	120	69	69	70	0.039	0.53	0		
1		10	380	183	19.7	478	72	72	98	66	565	664	420	467	511	1432		135	171.0	120	73	73	79	567.8	120	71	69	78	0.039	0.85	0		
2		20	240	65	18.10	482	73	73	99	67	948	642	452	525	570	1433		135	193.4	120	74	74	82	570.2	120	72	70	81	0.039	0.85	0		
3		30	120	24	17.64	462	75	75	101	68	966	650	492	564	570	1433		135	195.7	120	75	74	83	572.5	120	73	71	82	0.039	0.85	0		
4		40	160	15	10.38	403	75	75	96	68	806	660	523	569	574	1006		135	198.1	120	76	75	83	574.9	120	75	73	82	0.039	0.85	0		
5		50	40	57	8.13	356	75	75	93	69	667	669	503	537	578	888		135	200.5	120	78	77	83	577.3	120	77	74	82	0.039	0.85	0		
6		60	10	100	7.60	330	74	74	91	69	600	668	469	501	531	824		135	202.9	120	79	78	82	577.7	120	78	76	82	0.039	0.67	0		
7	6:5	70	0	11	7.12	320	75	75	90	69	574	672	456	484	534	809		135	204.1	120	80	78	82	580.9	120	78	77	81	0.039	0.61	0		
8		80																															
9		90																															
10		100																															
11		110																															
12		120																															
13		130																															
14		140																															
15		150																															
16		160																															
17		170																															
18		180																															
19		190																															
20		200																															
21		210																															
22		220																															
23		230																															
24		240																															
25		250																															
26		260																															
27		270																															
28		280																															
29		290																															
30		300																															
31		310																															
32		320																															
33		330																															
34		340																															
35		350																															
36		360																															
37		370																															
38		380																															
39		390																															
40		400																															
41		410																															
42		420																															
43		430																															
44		440																															
45		450																															
46		460																															
47		470																															
48		480																															

65 MIN
 1.826 Kg/Hr

COMMENTS:
 TEST LOADED IN 15 SECONDS DOOR OPEN 3:00 AIR LEFT FULL OPEN

APPENDIX B

INTRODUCTION

This document provides a step by step guide for the technician conducting tests to EPA standard requirements. Procedures outlined here, when followed, will result in tests in conformance with EPA Methods 28 and 5G-3. This guide cannot cover every possible contingency that may develop during a particular test program. Many questions that may arise can be answered by a complete understanding of the test standards and their intent. When in doubt on any detail check with the laboratory manager and be sure you understand the procedures involved.

The primary measurements to be obtained are particulate emission data and efficiency data. The technician's duties include the following steps. It is critical that all spaces on the data forms be properly filled in. Each test must be represented by a complete record of what was done and when.

- I. APPLIANCE INSPECTION AND SET-UP
 - A. Incoming Inspection
 - B. Unit Set-Up

- II. SAMPLING SYSTEMS - SET-UP
 - A. Gas Analysis
 - B. Dilution Tunnel

- III. TEST CONDUCT
 - A. Pre-Test Fuel Load
 - B. Test Fuel Load
 - C. Unit Start - up
 - D. Test Run

- IV. POST TEST PROCEDURE
 - A. Leak Checks
 - B. Particulate Sample Recovery

The technician running this test must be familiar with the following EPA documents that are to be kept in the laboratory at all times.

- 1. Method 28
- 2. Method 28A
- 3. Method 5G-3
- 4. Method 5H

I. APPLIANCE INSPECTION AND SET-UP

A. Incoming Inspection

1. Check for completeness of unit including parts, accessories, installation and operating instructions, drawings and specifications, etc. Note any discrepancies or missing parts.
2. Check for shipping damage. If damage has occurred, notify the laboratory manager. In some cases repairs may be made, provided the manufacturer and laboratory manager concur that repairs will not affect the units performance. If damage is irreparable, a new unit will need to be obtained.
3. Note whether unit is catalytic or non-catalytic.
4. Mark unit with manufacturer's name, model number, work order number and date received.
5. If unit is safety listed, note label data including listing agency and serial number.

B. Unit Set-Up

1. All units must be operated in-house for a break-in period as follows (the unit may be connected to a lab chimney). NOTE: Inserts are tested as if they are freestanding stoves.
 - a. Non-catalytic units: 10 hours minimum burn time with a stack temperature of at least 2501 Fahrenheit (medium burn rate, Douglas Fir scrap or cordwood.) A stack thermocouple must be installed and stack temperature recorded at 1-hour intervals or on chart recorder.
 - b. Catalytic units: 50 hours minimum burn time with catalyst temperature in excess of 8001 Fahrenheit (medium burn rate, Douglas Fir scraps or cordwood). Record catalyst temperature at 1-hour intervals or on chart recorder.
2. Once break-in is completed, allow unit to cool then clean unit thoroughly.

3. Thermocouples must be attached to surfaces of unit prior to testing. EPA requires a thermocouple on the outside bottom of the firebox. This must be installed prior to putting the unit on the scale. In some cases the required thermocouple locations will be inaccessible on finished units. Check with the laboratory manager if problems are encountered in proper thermocouple attachment.
4. Prior to placing unit on scale, the scale must be turned on and allowed to warm up for 1-hour minimum.
5. Place unit on scale and align so chimney will be centered in hood. Record the weight of the unit and all accessories. (Do not weight with chimney attached.)
6. Chimney and connector should be cleaned with a wire brush prior to mounting. Attach chimney and connector then seal all joints. Be sure single wall stove pipe terminates and insulated pipe starts at proper level above scale platform. Chimney must be supported from scale so that it does not touch test enclosure or hood walls.
7. Measure firebox dimensions and record on appropriate data form. Make a three dimensional sketch of the firebox including firebrick, baffles, and obstructions. Calculate firebox volume in cubic feet. See Section 6.2.4 of EPA Method 28 for details.
8. If unit is equipped with a catalyst additional thermocouples must be installed downstream of, and inside catalyst (upstream optional).
9. Plug thermocouples into data acquisition system jacks and verify that all instrumentation is working properly.
10. Dilution tunnel must be cleaned prior to each certification test series, and at anytime a higher burn rate follows a lower burn rate.

II. SAMPLING SYSTEMS SET-UP

A. Gas Analysis

1. All instruments should be turned on and allowed to warm up for 1-hour minimum.
2. Prior to calibrating, make sure that the outlet pressure on each calibration gas bottle reads 10 PSI. Adjust flow meters at each gas analyzer to required flow.

All gas analyzers (CO₂, CO, O₂) are zeroed on nitrogen. The O₂ analyzer is spanned on air and set for 20.93%. CO₂ and CO analyzers are spanned with their respective gases.

Calibrate analyzers as follows:

- a. With calibration switch at "SPAN", adjust all span controls to values specified on span gas label.
 - b. Switch to "ZERO" and adjust zero controls to provide 0.00 readout on all analyzers.
 - c. Repeat a. and b. until no further adjustment is required.
 - d. Record these values on the appropriate data sheet.
 - e. Switch to "CAL." and record all analyzer values.
3. Response time synchronization check.
 - a. With switch at "SAMPLE" and no fire in unit, allow readings to stabilize (O₂ analyzer should read 20.93, CO and CO₂ should read 0.00).
 - b. Switch to "CAL" setting and start the stopwatch. Note the time required for each unit to reach the calibration gas bottle value. If all three analyzers reach this value within 5 seconds of each other, synchronization is adequate. If not, contact the laboratory manager. Synchronization is adjusted by either internal instrument setting or adjustment of sample line length.
 - c. Use EPA Method 5H 6.7-6.9 procedures to check calibration of instruments.

4. Sample clean-up train.

- a. Load a new filter in 4-inch glass filter holder.
- b. Load four Impingers as follows.

#1: 100 ml. distilled water and 5 ml. H_2SO_4

#2: 100 ml. distilled water and 5 ml. H_2SO_4

#3: Empty

#4: 200-300 grams Drierite.

- c. Place Impingers in container and connect with greased "U TUBES". (Grease carefully on bottom half of ball joint so that grease will not get into tubes.)
- d. Connect filter to impinger #1 and sample line to impinger #4.
- e. Connect stack probe to filter.
- f. Leak check system as follows.
 - 1) Plug probe.
 - 2) Turn on sample system and increase flow rate slowly.
 - 3) Set vacuum adjust valve to obtain a vacuum of 10 inches mercury.
 - 4) If sapphire float in rotometer does not stabilize below 10 on scale, system must be resealed.
 - 5) Repeat leak check procedure until satisfactory results are obtained.
 - 6) Unplug probe slowly, then decrease flow rate slowly before shutting off system.
- g. Just prior to starting test, fill impinger container with ice.

B. Dilution Tunnel Sample Train Set-Up:

1. Filters and holders.

- a. Clean probes and filter holder front housings carefully and desiccate to a constant weight prior to use.
- b. Filters and filter probe combinations should be numbered and labeled prior to use.
- c. Weigh desiccated filters and probe filter units on analytical balance. Record weights on appropriate form. Note that probe and front half of front filter holder is to be weighed as a unit.
- d. Carefully assemble filter holder units and connect to sampling systems.
- e. Check Silica gel columns for adequate dry absorbent (blue color).

2. Leak checking.

- a. Each sample system is to be checked for leakage prior to inserting probes in tunnel.
- b. Plug probes and start samplers. Adjust pump bypass valve to produce a vacuum reading of 10 inches mercury. NOTE: During test, highest vacuum recorded is required for posttest leak check.
- c. Allow vacuum indication to stabilize at 10" mercury, record dry gas meter readings, (DGM₁, DGM₂). At a convenient DGM value start stopwatch. Time for 1 minute then stop vacuum pumps. Record dry gas meter readings again, (DGM₃, DGM₄). NOTE: If rotometer ball is floating above the 5-mm mark, system is leaking too much and all seals should be checked.
- d. Calculate leakage rate as follows.

$$\text{System 1: } DGM_3 - DGM_1 = CFM_1$$

$$\text{System 2: } DGM_4 - DGM_2 = CFM_2$$

If CFM₁ or CFM₂ is greater than 0.02 cfm, or $\frac{1}{S}$ greater than 0.04 x Sample Rate, leakage is unacceptable and system must be resealed.

For most tests the sample rate will be 0.25 cfm, thus leakage rates in excess of 0.04 x 0.25 = 0.010 cfm are not acceptable.

- e. To prevent contamination, do not insert probes in tunnel until the start of the test run.

III. TEST CONDUCT

A. Pre-Test Fuel Load

1. Using 2x4 Douglas Fir cut enough pieces to approximate test load weight. (Piece length must be greater than 1/3 of the test load length.)
2. Measure percent moisture content using Delmhorst moisture meter. The average percent moisture must be within 19 to 25 percent.

B. Test Fuel Load

1. Determine optimum load weight by multiplying firebox volume (cubic feet) by 7. This is the ideal load weight.
2. Determine piece size mix i.e. <1.5 cubic feet volume use 2x4's only; 1.5 ft³ to 3.0 ft³ use a mix of 2.4's and 4x4's; >3.0 ft³ use only 4x4's. Ideal length is 5/6 of the longest firebox dimension.
3. Weigh out test load and appropriate number of spacers and adjust weight by shortening or lengthening all pieces equally if necessary.
4. Construct test loads by attaching spacers as shown in EPA Method 28.
5. Measure and record moisture content of each fuel piece (use three sides). Determine if fuel load moisture content is within required range (19-25%). If not, construct new fuel pieces using wood with required moisture content.
All wood in the humidity chamber is Douglas Fir and should be within range. Contact laboratory manager if you cannot find suitable pieces.

C. Unit Start-Up

1. With all doors and air controls closed, zero draft Magnehelic using screw located at bottom of meter.
2. Before lighting a fire, turn on dilution tunnel and set flow rate to 140 scfm (approximately 715 fpm) if burn rate is to be less than 3 kg/hr. For higher burn rates set flow for a 150:1 air fuel ratio (see chart for approximate values).
3. Check draft imposed on cold stove. All inlets must be closed and a draft gauge in the chimney. If draft is greater than 0.005 inches water column, adjust tunnel to stack gap until draft is less than 0.005 inches water column.

4. With hot wire anemometer check for ambient airflow around unit (must be less than 50 ft/min).
5. Zero scale and start fire with newspaper and Douglas Fir kindling. (Make sure stack sample probe is on the unit.)
6. Once kindling is burning well, add preload fuel. Operate at high fire for sufficient time to get fuel load burning well. Then adjust settings to intended test run levels.
7. Perform the dilution tunnel traverse as prescribed in Method 28, Section 6.3. (Pitot tube should be carefully cleaned prior to each test.)
8. Pretest load must burn for a minimum of 1 hour. Record stove surface, catalyst, room and flue temperatures.
9. Stir fire often during preburn (after a reading) to get a good coal bed. Fire can only be raked once (door open 1 minute or less) during the 15 minutes prior to the start of the test.

D. Test Run

1. Stack gas analyzers should be on and in the sample mode.
2. When the fuel bed is between 20-25% of the test load weight the test is to be started.
 - a. Insert the sample probes into the tunnel being careful not to hit sides of tunnel with probe tip.
 - b. Check tunnel Pitot tube for proper position.
 - c. Record initial readings.
 - d. Turn on probe sample systems and start timing test.
 - e. Tare platform scale.
 - f. Open stove doors and load stove. Close door or follow manufacturer's start-up procedures. Five minutes is the maximum time before all doors and controls must be set to final positions for duration of test.
 - g. Record length of time door and bypass are open, include any air control setting adjustments.
 - h. Every 10 minutes record the following:
 - 1) Dry gas meter readings.
 - 2) Weight remaining.
 - 3) All thermocouple temperatures.
 - 4) Tunnel Pitot tube reading.
 - 5) Draft reading.
 - 6) Rotometer readings.
 - i. Filter temperatures shall not exceed 901F anytime during the test. If approaching 901F turn on cooling pump. Filters must be kept above the dilution tunnel wet bulb temperature in order to prevent condensation.
 - j. Regularly check impinger for ice level during test.
 - k. After 30 seconds of 0.00 lbs. weight, and on the minute, shut off sample trains and record last reading.
 - l. Record final dry gas meter values.

IV. POST TEST PROCEDURES

A. LEAK CHECKS

1. Dilution Tunnel

- a. Remove both sample probes from tunnel and plug with rubber stopper.
- b. Turn on sample system and set vacuum to 10" mercury or to the highest value reached during the test.
- c. At a convenient value start stop watch. Record DGM starting value.
- d. After 1 minute stop sample system and record ending DGM value.
- e. Calculate leakage rate per pre-test description (see II.B.2.c.).

2. Gas Analyzers

- a. Set stack sample flow to about 75 mm on the rotometer.
- b. Plug with rubber stopper.
- c. Adjust vacuum to 10" mercury.
- d. Let system stabilize then record rotometer readings.
- e. If rotometer readings do not equal zero check with laboratory manager.
- f. SLOWLY unplug probe and decrease flow rate to zero.
- g. Turn off stack sampling system.
- h. Zero, span and calibrate the analyzers (see Gas Analysis).
RECORD ONLY these meter values.

B. Particulate Sample Recovery

1. Disassemble filter holder and scrape gasket with scalpel. Collect all loose material on filters.
2. Weigh and record probes and filters for each train. NOTE: 24 hours of desiccation must pass before final "no change" weight values can be recorded.
3. Weigh and record probes and fillers at 2-hour intervals until weight change between weighing is less than 0.5 mg.
- 4.

In order to meet the requirements of section 60.535(g) of the EPA's 40CFR Part 60 Standards of Performance for New Stationary Sources; New Residential Wood Heaters, Intertek Testing Services seals certified wood heaters by strapping the unit to a pallet and covering the unit with stretch wrap. A copy of the EPA certificate is attached and our G mark stamped on the stretch wrap in various positions and then another layer of stretch wrap is used to cover the markings and copy of the certificate. Any breaking of the stretch wrap seal will be easily noticeable. The unit is then shipped back to the manufacturer.

APPENDIX C

		Manufacturer:		Morso					
		Model:		1410					
		Date:		02/03/00					
		Run:		1					
		Project #:		31218					
		Test Duration:		143					
		Total Gas Volume (DGM 1):		32.71623					
		Total Gas Volume (DGM 2):		33.25849					
		Average Barometric Pressure:		28.755					
		Molecular Weight:		28.56					
		Pitot Correction:		0.9795					
		Calibration Factor (DGM #1):		1.0157					
		Calibration Factor (DGM #2):		1.0361					
		(1) VS:		0.045724					
		(2) VS:		0.044979					
								Filter	Filter
								Face	Face
Elapsed	DGM 1	DGM 1	DGM 1	DGM 2	DGM 2	DGM 2	Tunnel	Velocity	Velocity
Time	Reading	Inlet T	Outlet T	Reading	Inlet T	Outlet T	Dry Bulb	DGM 1	DGM 2
0	106.4	77	77	484.1	74	74	83		
10	108.8	77	78	486.4	75	74	86	19.83	19.50
20	111.2	78	78	488.8	76	75	85	19.81	20.31
30	113.6	79	78	491.2	77	76	85	19.79	20.27
40	116.0	79	79	493.6	77	76	86	19.78	20.27
50	118.4	80	79	496.0	78	77	87	19.76	20.23
60	120.8	80	80	498.3	79	78	85	19.74	19.35
70	123.2	81	80	500.7	80	78	82	19.72	20.17
80	125.6	81	81	503.1	80	79	81	19.70	20.15
90	128.0	81	81	505.5	81	80	81	19.70	20.12
100	130.4	81	81	507.8	81	81	80	19.70	19.26
110	132.8	82	81	510.3	81	81	79	19.68	20.94
120	135.2	81	81	512.6	81	81	79	19.70	19.26
130	137.6	82	81	515.0	81	81	79	19.68	20.10
140	140.0	81	82	517.4	81	81	77	19.68	20.10
143	140.7	82	82	518.2	81	82	77	19.12	22.31

Proportional Rate Calculations				(EPA Formulas from PR5G)				
Stack area (ft ²):	0.1963			Manufacturer:	Morso			
Wood moisture (% wet):	18.05			Model:	1410			
Load Weight (lbs wet):	5.1			Date:	02/03/00			
Burn Rate (Dry kg/hr):	0.794			Run:	1			
Final Temperature (DGM #1) Degrees Rankin:				540.031				
Final Temperature (DGM #2) Degrees Rankin:				538.656				
Final Tunnel Temperature Degrees Rankin:				542.000				
Final Tunnel Velocity (feet per second):				13.5132264				
Standardized Tunnel Flow (dscfm):				142.992909				
	Average	Average						
	Inlet +	Inlet +						
	Outlet	Outlet			#1	#2		
	Tunnel	Tunnel			dDGM	dDGM		
Velocity	Temp.	Temp.			Vol.Std.	Vol.Std.		
	Meter 1	Meter 2			(ft ³)	(ft ³)	Time	
	Deg. R	Deg. R	PR1	PR2				
0.040	13.484	537.0	534.0				0	
0.040	13.521	537.5	534.5	101.21	98.03	2.300	2.261	10
0.040	13.509	538.0	535.5	101.02	102.01	2.298	2.355	20
0.041	13.677	538.5	536.5	99.69	100.57	2.296	2.351	30
0.039	13.351	539.0	536.5	102.21	103.21	2.294	2.351	40
0.041	13.702	539.5	537.5	99.69	100.57	2.292	2.347	50
0.040	13.509	540.0	538.5	100.65	97.22	2.290	2.245	60
0.041	13.639	540.5	539.0	99.05	99.83	2.288	2.340	70
0.040	13.459	541.0	539.5	100.09	100.88	2.286	2.338	80
0.041	13.626	541.0	540.5	98.86	99.46	2.286	2.334	90
0.041	13.614	541.0	541.0	98.77	95.14	2.286	2.234	100
0.040	13.434	541.5	541.0	99.81	104.60	2.283	2.429	110
0.040	13.434	541.0	541.0	99.91	96.23	2.286	2.234	120
0.040	13.434	541.5	541.0	99.81	100.42	2.283	2.331	130
0.040	13.409	541.5	541.0	99.63	100.23	2.283	2.331	140
0.040	13.409	542.0	541.5	98.11	104.31	0.720	0.776	143

Manufacturer:		Morso							
Model:		1410							
Date:		02/04/00							
Run:		2							
Project #:		31218							
Test Duration:		117							
Total Gas Volume (DGM 1):		27.52174							
Total Gas Volume (DGM 2):		27.60526							
Average Barometric Pressure:		29.25							
Molecular Weight:		28.56							
Pitot Correction:		0.9826							
Calibration Factor (DGM #1):		1.0157							
Calibration Factor (DGM #2):		1.0361							
(1) VS:		0.053772							
(2) VS:		0.053609							
								Filter Face	Filter Face
Elapsed Time	DGM 1 Reading	DGM 1 Inlet T	DGM 1 Outlet T	DGM 2 Reading	DGM 2 Inlet T	DGM 2 Outlet T	Tunnel Dry Bulb	Velocity DGM 1	Velocity DGM 2
0	140.8	77	76	518.2	74	72	73		
10	143.1	77	77	520.5	74	73	93	19.58	19.64
20	145.5	77	77	522.9	75	74	88	20.19	20.69
30	147.9	79	78	525.3	77	75	87	20.14	20.64
40	150.3	78	78	527.7	77	76	87	20.15	20.62
50	152.7	79	78	530.1	79	78	85	20.14	20.54
60	155.1	79	78	532.5	79	79	83	20.14	20.52
70	157.5	79	79	534.8	79	79	81	20.12	19.67
80	160.0	80	80	537.2	79	79	80	20.92	20.52
90	162.4	80	80	539.6	79	79	79	20.08	20.52
100	164.8	80	80	542.0	80	80	79	20.08	20.48
110	167.2	8	80	544.3	80	80	78	21.51	19.63
117	168.9	80	80	546.0	80	80	78	20.32	20.73

Proportional Rate Calculations				(EPA Formulas from PR5G)				
Stack area (ft2):	0.1963			Manufacturer:	Morso			
Wood moisture (% wet):	18.82			Model:	1410			
Load Weight (lbs wet):	5.22			Date:	02/04/00			
Burn Rate (Dry kg/hr):	0.986			Run:	2			
Final Temperature (DGM #1) Degrees Rankin:				535.923				
Final Temperature (DGM #2) Degrees Rankin:				537.538				
Final Tunnel Temperature Degrees Rankin:				542.385				
Final Tunnel Velocity (feet per second):				13.3778163				
Standardized Tunnel Flow (dscfm):				143.8948				
		Average	Average					
		Inlet +	Inlet +					
		Outlet	Outlet			#1	#2	
	Tunnel	Temp.	Temp.			dDGM	dDGM	
Tunnel	Velocity	Meter 1	Meter 2			Vol.Std.	Vol.Std.	
Velocity	Ft/Sec	Deg. R	Deg. R	PR1	PR2	(ft3)	(ft3)	Time
0.039	13.121	536.5	533.0					0
0.039	13.364	537.0	533.5	98.53	98.57	2.271	2.279	10
0.039	13.304	537.0	534.5	101.16	103.36	2.342	2.400	20
0.041	13.628	538.5	536.0	98.30	100.44	2.336	2.394	30
0.041	13.628	538.0	536.5	98.39	100.34	2.338	2.391	40
0.040	13.436	538.5	538.5	99.34	101.03	2.336	2.383	50
0.040	13.412	538.5	539.0	99.16	100.75	2.336	2.380	60
0.040	13.387	539.0	539.0	98.88	96.37	2.334	2.281	70
0.040	13.375	540.0	539.0	102.72	100.47	2.426	2.380	80
0.040	13.362	540.0	539.0	98.52	100.38	2.329	2.380	90
0.040	13.362	540.0	540.0	98.52	100.19	2.329	2.376	100
0.040	13.350	504.0	540.0	105.45	95.93	2.496	2.277	110
0.039	13.182	540.0	540.0	100.86	102.58	1.650	1.683	117

Manufacturer: Morso
 Model: 1410
 Date: 02/07/00
 Run: 3
 Project #: 31218
 Test Duration: 82
 Total Gas Volume (DGM 1): 19.108958
 Total Gas Volume (DGM 2): 19.27223
 Average Barometric Pressure: 29.37
 Molecular Weight: 28.56
 Pitot Correction: 0.9856
 Calibration Factor (DGM #1): 1.0157
 Calibration Factor (DGM #2): 1.0361

(1) VS: 0.0771683
 (2) VS: 0.0765145

Elapsed Time	DGM 1 Reading	DGM 1 Inlet T	DGM 1 Outlet T	DGM 2 Reading	DGM 2 Inlet T	DGM 2 Outlet T	Tunnel Dry Bulb	Filter Face	Filter Face
								Velocity DGM 1	Velocity DGM 2
0	169.0	76	76	546.1	73	73	85		
10	171.3	77	77	548.4	75	74	102	19.45	20.04
20	173.7	78	78	550.7	76	74	99	20.24	19.89
30	176.1	78	78	553.1	76	75	97	20.24	20.74
40	178.5	79	78	555.4	78	76	96	20.22	19.82
50	180.9	81	80	557.8	79	77	93	20.14	20.64
60	183.3	81	80	560.2	80	80	90	20.14	20.57
70	185.7	83	82	562.6	82	80	88	20.07	20.53
80	188.1	83	83	564.9	83	81	86	20.05	19.64
82	188.6	83	82	565.4	82	82	86	20.91	21.34

Proportional Rate Calculations				(EPA Formulas from PR5G)				
Stack area (ft2):	0.1963	Manufacturer:	Morso					
Wood moisture (% wet):	18.56	Model:	1410					
Load Weight (lbs wet):	5.16	Date:	02/07/00					
Burn Rate (Dry kg/hr):	1.395	Run:	3					
Final Temperature (DGM #1) Degrees Rankin:	539.650							
Final Temperature (DGM #2) Degrees Rankin:	537.800							
Final Tunnel Temperature Degrees Rankin:	552.200							
Final Tunnel Velocity (feet per second):	13.57128963							
Standardized Tunnel Flow (dscfm):	143.9693444							
	Average Inlet + Outlet Temp. Meter 1	Average Inlet + Outlet Temp. Meter 2			#1 dDGM Vol. Std. (ft3)	#2 dDGM Vol. Std. (ft3)		
Tunnel Velocity Ft/Sec	Deg. R	Deg. R	PR1	PR2				Time
0.039	13.281	536.0	533.0					0
0.039	13.486	537.0	534.5	99.18	101.31	2.257	2.325	10
0.041	13.791	538.0	535.0	100.35	97.82	2.347	2.308	20
0.040	13.597	538.0	535.5	101.42	103.06	2.347	2.406	30
0.040	13.585	538.5	537.0	101.23	98.40	2.345	2.299	40
0.040	13.548	540.5	536.0	100.58	102.21	2.337	2.395	50
0.041	13.679	540.5	540.0	99.08	100.31	2.337	2.386	60
0.040	13.487	542.5	541.0	99.76	101.18	2.328	2.381	70
0.041	13.629	543.0	542.0	98.26	95.42	2.326	2.278	80
0.041	13.629	542.5	542.0	102.45	103.72	0.485	0.495	82

Manufacturer:	Morso
Model:	1410
Date:	02/08/00
Run:	4
Project #:	31218
Test Duration:	65
Total Gas Volume (DGM 1):	15.23412
Total Gas Volume (DGM 2):	15.60403
Average Barometric Pressure:	29.39
Molecular Weight:	28.56
Pitot Correction:	0.9865
Calibration Factor (DGM #1):	1.0157
Calibration Factor (DGM #2):	1.0361

(1) VS: 0.095744
(2) VS: 0.093474

Elapsed Time	DGM 1 Reading	DGM 1 Inlet T	DGM 1 Outlet T	DGM 2 Reading	DGM 2 Inlet T	DGM 2 Outlet T	Tunnel Dry Bulb	Filter Face	Filter Face
								Velocity DGM 1	Velocity DGM 2
0	188.6	72	72	565.4	69	69	80		
10	191.0	73	73	567.8	71	69	98	20.44	20.97
20	193.4	74	74	570.2	72	70	99	20.40	20.93
30	195.7	75	74	572.5	73	71	101	19.53	20.02
40	198.1	76	75	574.9	75	73	96	20.34	20.81
50	200.5	78	77	577.3	77	74	93	20.27	20.75
60	202.9	79	78	579.7	78	76	91	20.23	20.70
65	204.1	80	78	580.9	78	77	90	20.21	20.68

Proportional Rate Calculations				(EPA Formulas from PR5G)				
Stack area (ft2):	0.1963	Manufacturer:	Morso					
Wood moisture (% wet):	18.65	Model:	1410					
Load Weight (lbs wet):	5.36	Date:	02/08/00					
Burn Rate (Dry kg/hr):	1.826	Run:	4					
Final Temperature (DGM #1) Degrees Rankin:		535.500						
Final Temperature (DGM #2) Degrees Rankin:		533.250						
Final Tunnel Temperature Degrees Rankin:		553.500						
Final Tunnel Velocity (feet per second):		13.4553456						
Standardized Tunnel Flow (dscfm):		142.501089						
	Average	Average						
	Inlet +	Inlet +						
	Outlet	Outlet			#1	#2		
	Temp.	Temp.			dDGM	dDGM		
Tunnel	Tunnel	Meter 1	Meter 2		Vol.Std.	Vol.Std.		
Velocity	Ft/Sec	Deg. R	Deg. R	PR1	PR2	(ft3)	(ft3)	Time
0.039	13.227	532.0	529.0					0
0.039	13.446	533.0	530.0	102.06	102.22	2.371	2.432	10
0.041	13.799	534.0	531.0	99.44	99.60	2.367	2.428	20
0.040	13.654	534.5	532.0	96.57	96.62	2.266	2.322	30
0.040	13.593	535.5	534.0	100.13	100.00	2.360	2.414	40
0.039	13.386	537.5	535.5	100.75	100.71	2.351	2.407	50
0.039	13.361	538.5	537.0	100.38	100.25	2.347	2.401	60
0.038	13.177	539.0	537.5	101.51	101.38	1.172	1.199	65

APPENDIX D

Intertek Testing Services

Warnock Hersey
Middleton, Wisconsin

Post Test Dry Gas Meter Calibration Data

Manufacturer: Moroso Model: 1410 Job Number: 31218 Date: 02/08/00 Tech: RA
 Barometric Press: 29.29 Calibration Factors: DGM#1: 1.0157 DGM#2: 1.0361 Std. Meter DGM#3: 1.0212

Standardized Meter # 3

Trial No.	Press Drop	Initial Ft. ³	Final Ft. ³	Change Ft. ³	Temp °F	Std. Ft. ³	Initial Ft. ³	Final Ft. ³	Change Ft. ³	Temp °F	Std Ft. ³	Cal Factor
1	0.055	317.491	319.78	2.2890	72	2.2711	205.137	207.58	2.443	77	2.3884	0.9509
2	0.055	319.78	322.139	2.359	72	2.3406	207.58	209.972	2.392	77	2.3385	1.0009
3	0.055	322.139	324.458	2.319	72	2.3009	209.972	212.45	2.478	77	2.4226	0.9497
Average:												0.9672

System # 1

Previous Call Factor: 1.0157 Avg. Cal. Factor: 0.9672 divided by Previous Cal Factor: 1.0157 equals Present Deviation: 4.7783

Standardized Meter #3

Trial No.	Press Drop	Initial Ft. ³	Final Ft. ³	Change Ft. ³	Temp °F	Std. Ft. ³	Initial Ft. ³	Final Ft. ³	Change Ft. ³	Temp °F	Std Ft. ³	Cal Factor
1	0.055	325.815	328.283	2.4680	72	2.4487	582.135	584.578	2.443	75	2.4455	1.0013
2	0.055	328.283	330.771	2.4880	72	2.4685	584.578	587.029	2.451	76	2.4489	1.0080
3	0.055	330.771	333.262	2.4910	72	2.4715	587.029	589.475	2.446	76	2.4439	1.0113
Average:												1.0069

System # 2

Previous Call Factor: 1.0361 Avg. Cal. Factor: 1.00688 divided by Previous Cal Factor: 1.0361 equals Present Deviation: 2.82020



Manufacturer _____ Model _____ Date _____ Page ____ of ____

Job # _____ Run _____ Tech _____
POST TEST DRY GAS METER CALIBRATION DATA
MANUFACTURER: MORG MODEL: 1410 LTO: 2/21/8 DATE: 2-8-82 TECHNICIAN: RA

BAROMETRIC PRESSURE: 29.29 CALIBRATION FACTOR DGM#1: 1.0157 DGM#2: 1.0361 STANDARDIZED DGM#3: 1.0212

STANDARD METER

TRAIL NO.	PRESS DROP	METER #1			TEMP °F	CHANGE FT. ³	INITIAL FT. ³	FINAL FT. ³	STD FT. ³	EQUALS	MULTIPLIED *100	PREVIOUS CAL.FACTOR	DEVIATION PERCENT
		FINAL FT. ³	INITIAL FT. ³	CHANGE FT. ³									
1	.055	319.780	317.491	2.2890	72	2.2711	207.580	205.137	2.4413	77	2.4413	2.3884	1.003
2	.055	322.139	319.780	2.359	72	2.3406	209.972	207.580	2.392	77	2.392	2.400	1.0009
3	.055	324.580	322.139	2.319	72	2.4495	212.450	209.972	2.478	77	2.478	2.4226	1.0072

AVERAGE CALIBRATION FACTOR: 1.9672

PREVIOUS CAL. FACTOR

1.0157	-	9672	1	1.0157	=	*100	4.7783 %
--------	---	------	---	--------	---	------	----------

STANDARD METER

TRAIL NO.	PRESS DROP	METER #2			TEMP °F	CHANGE FT. ³	INITIAL FT. ³	FINAL FT. ³	STD FT. ³	EQUALS	MULTIPLIED *100	PREVIOUS CAL. FACTOR	DEVIATION PERCENT
		FINAL FT. ³	INITIAL FT. ³	CHANGE FT. ³									
1	.055	328.233	325.815	2.4180	72	2.4487	584.578	582.135	2.443	75	2.4455	2.4455	1.003
2	.055	330.771	328.283	2.488	72	2.4685	587.029	584.578	2.451	76	2.4489	2.4489	1.0080
3	.055	333.222	330.771	2.4910	72	2.4715	589.475	587.029	2.446	76	2.4439	2.4439	1.0113

AVERAGE CALIBRATION FACTOR: _____

PREVIOUS CAL. FACTOR

1.0361	-	1.0069	1	1.0361	=	*100	2.820 %
--------	---	--------	---	--------	---	------	---------

PERCENT OF DEVIATION MUST BE LESS THAN 5 %. IF DEVIATION IS MORE THAN 5 %, THE UPDATED CALIBRATION FACTOR MUST BE USED.

APPENDIX E

Manufacturer MORSO Model 1410 Date 2-8-00

Job # 31218 Run POST TEST Tech RA

POST TEST 5-POINT GAS ANALYZER CHECK

	CO		CO ₂		O ₂	
	Actual	Should Be	Actual	Should Be	Actual	Should Be
Zero Gas		0		0		0
Span Gas		9.99		24.65		20.93
Cal Gas #1		.991		10.02		10.01
Deviation	.97	2.12	9.69	3.29	10.13	1.20
Cal Gas #2	2.35	2.36	5.78	5.88	5.69	5.55
Deviation		.42		1.70		2.52
Cal Gas #3		7.68		19.86		17.16
Deviation	7.66	1.04	19.28	2.97	17.36	2.80
Average Deviation		1.19		2.65		2.17

Manufacturer: Morso
 Project No: 31218
 Model: 1410
 Date: 02/08/00

	CO		CO2		O2	
	Actual	Should be	Actual	Should be	Actual	Should be
Zero Gas	0	0	0	0	0	0
Span Gas	9.99	9.99	24.63	24.63	20.93	20.93
Cal GAS #1 Deviation	0.97	0.991 2.12%	9.69	10.02 3.29%	10.13	10.01 1.20%
Cal GAS #2 Deviation	2.35	2.36 0.42%	5.78	5.88 1.70%	5.69	5.55 2.52%
Cal GAS #3 Deviation	7.6	7.68 1.04%	19.27	19.86 2.97%	17.64	17.16 2.80%
Average Deviation		1.19%		2.65%		2.17%

ITS EQUIPMENT CALIBRATION RECORD

ITS# 56

DESCRIPTION: Chart Recorder

MANUFACTURER: Cole Parmer

SERIAL #: 221068 MODEL: 8376-XX

EQUIPMENT LOCATION: E + E

PURPOSE & ACCURACY: ±0.2°C

CALIBRATION SPECIFICATIONS/INTERVAL: 1 yr.

CALIBRATION DATE	NEXT CALIBRATION	CALIBRATION AGENCY	CAL. BY	RESULTS/ADJUST.
<u>11/24/98</u>	<u>11/24/99</u>	<u>Cal Lab</u>		
<u>11/22/99</u>	<u>11/22/00</u>	<u>"</u>		

MAINTENANCE AND REPAIR:

DATE OUT OF SERVICE	DATE BACK IN SERVICE	REPAIR AGENCY	DESCRIPTION OF REPAIR



CERTIFICATE OF CALIBRATION

Cert. No. 1041317

GAJ



Customer

Intertek Testing Services
8431 Murphy Dr.
Middleton, WI 53562

Equipment

Manufact: Cole Parmer
Descript: Chart Recorder
Model #: 8376-XX
Serial #: 221068
I.D. #: 000056

Calibration Date: 11/22/1999

Recalibration Date: 11/22/2000

Received Condition: Fully operational and within tolerance

Work Performed: No adjustments required and calibrated to manufacturers specifications using
manufacturers procedure

Test Conditions: Temperature: 68°F Humidity: 45% Technician: Jim Goff On site

Standards Used

1239 Datron 4800 Multifunction Calibrator 01/31/2000

1390 Fluke 743B Process Calibrator: 01/31/2000

This instrument was calibrated with a minimum 4:1 TWR/TAR unless otherwise stated. These represent best uncertainties. Actual uncertainties are available upon request.

Best Measurement Uncertainty

DC Voltage ± 8.5 ppm

Temperature ± 0.2 °C

Reviewed and approved by
Issue Date: 11/23/1999

Mike Boothe
Quality Team Member

This Certificate may not be reproduced except in its entirety without the written approval of CAL LAB Co., Inc.

This Report Certifies that all Calibration Equipment used in the test is traceable to the NIST, and the test was performed in accordance to ANSI/NCSL Z540-1-1994 (FORMERLY MIL-STD 45662A)

17035 Westview Ave.
South Holland, IL 60473

CAL LAB Co. Inc.
800-373-1759

3695-K North 126th Street
Brookfield, WI 53005

ITS EQUIPMENT CALIBRATION RECORD

ITS# 54

DESCRIPTION: Digital Type K Thermocouple Meter

MANUFACTURER: Omega

SERIAL #: 21662 MODEL: 199-KF-A-X

EQUIPMENT LOCATION: EVE

PURPOSE & ACCURACY: ~~± 1°F~~ ± 2°F (1/11)

CALIBRATION SPECIFICATIONS/INTERVAL: 6 months

CALIBRATION DATE	NEXT CALIBRATION	CALIBRATION AGENCY	CAL. BY	RESULTS/ADJUST.
12/11/98	6/11/99	In house	RA	
6/11/99	12/11/99	"	RA	
1/14/00	7/14/00	"	RA	

MAINTENANCE AND REPAIR:

DATE OUT OF SERVICE	DATE BACK IN SERVICE	REPAIR AGENCY	DESCRIPTION OF REPAIR

ITS Intertek Testing Services NA Inc.

Middleton, Wisconsin

CALIBRATION DATE: 11-14-00
 REVIEWED BY: [Signature]

CALIBRATED BY: RA

DESCRIPTION: K-Meter (Omega)

MODEL: 199

SERIAL NUMBER: 21662

WHI INVENTORY #054
 (located in E&E Lab)

USING: OMEGA CL 6503 CALIBRATOR
 BK 2816 VOLTMETER

CALIBRATOR

METER

VOLTMETER

SET AT

_____ UNADJUSTED _____
 _____ _____ _____

Calibrator	Voltmeter	Meter	Dev. °F	Calibrator	Voltmeter	Meter	Dev. °F
31.4	30	31	.4	912.6	912	912	.6
115.1	113	113	2.1	912			
196.9	196	196	.9	1051.6	1051	1051	.6
278.5	279	279	.5	1111.7	1111	1111	.7
446.8	446	446	.8	1211.3	1212	1211	.3
530.0	528	528	2.	1372.5	1373	1373	.5
611.4	610	611	.4	1433.7	1436	1434	.7
712.8	711	711	.2	1516.6	1517	1515	1.6
832.6	831	831	1.6	1748.6	1749	1748	.6

AVERAGE 1852 °F

ITS EQUIPMENT CALIBRATION RECORD

ITS# 28

DESCRIPTION: Analytical Balance

MANUFACTURER: Ohaus

SERIAL #: 5336 MODEL: G110

EQUIPMENT LOCATION: E & E

PURPOSE & ACCURACY: ±.0001

CALIBRATION SPECIFICATIONS/INTERVAL: 6 months

CALIBRATION DATE	NEXT CALIBRATION	CALIBRATION AGENCY	CAL. BY	RESULTS/ADJUST.
6-2-97	12-2-97	In-house	RA	
6/25/98	12-25-98	"	WK	
12/11/98	6/11/99	"	RA	
6/1/99	12/1/99	"	RA	
1/14/00	7/14/00	"	RA	

MAINTENANCE AND REPAIR:

DATE OUT OF SERVICE	DATE BACK IN SERVICE	REPAIR AGENCY	DESCRIPTION OF REPAIR

ITS Intertek Testing Services NA Inc.

Middleton, Wisconsin

CALIBRATION DATE: 1-14-99
REVIEWED BY: [Signature]

CALIBRATED BY: RA

DESCRIPTION: Analytical Balance

MODEL: (Ohaus) Galaxy 110

SERIAL NUMBER: 5336

WHI INVENTORY #028

Ainsworth Class S Weight

WEIGHT	MEASURED	DEVIATION (g)
2 mg		
5 mg	.00506 5 mL	0
10 mg	.0099 G	.0001
20 mg	0200 G	0
50 mg	.05016	.0001
100 mg	1001 G	.0001
1 g	.9998 G	.0002
20 g	20.0003	.0003
50 g	50.0002	.0002
100 g	100.0001	.0001

AVERAGE DEVIATION = .00012 grams

ITS EQUIPMENT CALIBRATION RECORD

ITS# 22

DESCRIPTION: Manometer 0-1" Inclined

MANUFACTURER: _____

SERIAL #: 882 MODEL: 125 AV

EQUIPMENT LOCATION: Emissions Lab

PURPOSE & ACCURACY: ± 1% of FS (0.01 in)

CALIBRATION SPECIFICATIONS/INTERVAL: 6 mos.

CALIBRATION DATE	NEXT CALIBRATION	CALIBRATION AGENCY	CAL. BY	RESULTS/ADJUST.
3/17/94	9/17/94	Inhouse	WK	
10/1/94	4/1/95	"	WK	
4/11/95	10/11/95	"	RA	
10/16/95	4/16/96	"	RA	
4/19/96	10/19/96	"	WK	
10/9/96	4/9/97	"	RB	
5/14/97	11/14/97	"	RA	
12/16/97	6/16/98	"	RA	
8/12/98	2/12/99	"	RA	
1-22-99	7-22-99	"	RA	
7/16/99	1/16/00	"	RA	
1/14/00	7/14/00	"	RA	

MAINTENANCE AND REPAIR:

DATE OUT OF SERVICE	DATE BACK IN SERVICE	REPAIR AGENCY	DESCRIPTION OF REPAIR

ITS Intertek Testing Services NA Inc.

Middleton, Wisconsin

CALIBRATION DATE: 6/14/00
REVIEWED BY: [Signature]

CALIBRATED BY: R4

DESCRIPTION: Manometer Inclined 0-1"
Located in EE lab

MODEL: 125 AV

SERIAL NUMBER: 8 82

WHI INVENTORY #022

CHANGE THIS TO
1 TIME PER YEAR

MICROTECTOR	MANOMETER	DEVIATION IN.
.022	.034	.002
.051	.084	.018
.086	.166	.006
.113	.214	.012
.138	.262	.014
.165	.317	.013
.191	.364	.018
.239	.462	.016

AVERAGE DEVIATION = .0124 INCHES

Note: Microtector reading is exactly 1/2 of the manometer reading

ITS EQUIPMENT CALIBRATION RECORD

ITS# 021

DESCRIPTION: Alnor Velometer

MANUFACTURER: Alnor

SERIAL #: MD1057 MODEL: 8525

EQUIPMENT LOCATION: Calibrated - In-house

PURPOSE & ACCURACY: ±3% - 75-79° / ±4% - 68-86° / ±9% - 32-122°

CALIBRATION SPECIFICATIONS/INTERVAL: 6 months

CALIBRATION DATE	NEXT CALIBRATION	CALIBRATION AGENCY	CAL. BY	RESULTS/ADJUST.
10-30-96	4-30-97	Alnor Instruments		Was broken - repaired 10/96
12-4-96	6-4-97	In-house	RA	
6-2-97	12-2-97	"	RA	
12/12/97	6/12/98	"	RA	
8/11/98	2/11/99	"	RA	
1-22-99	7-22-99	"	RA	
7/16/99	1/16/00	"	RA	
7/14/00	7/14/00	"	RA	

MAINTENANCE AND REPAIR:

DATE OUT OF SERVICE	DATE BACK IN SERVICE	REPAIR AGENCY	DESCRIPTION OF REPAIR

ITS Intertek Testing Services NA Inc.

Middleton, Wisconsin

CALIBRATION DATE: 1-14-00
REVIEWED BY: [Signature]

CALIBRATED BY: RA

DESCRIPTION: Alnor Hot Wire Anemometer
Located in EE lab

MODEL: 8525

SERIAL NUMBER: MD 1057

WHI INVENTORY #021

PITOT TUBE IN TUNNEL CENTER.

Barometric Pressure:

Manometer Reading	Tunnel Temp	Static Pressure	Velocity ft/sec	ft/min	Velometer ft/min	Deviation
.056	69	.168	15.89	953.1	810	15.02%
.041	68	.111	13.57	814.0	730	10.32%
.026	68	.084	10.80	647.9	640	1.22%
.115	66	.353	22.77	1366.3	1170	14.37
.1262	66	.8	34.64	2078.2	1750	15.79
.28	66	.89	35.82	2151.8	1840	14.49

AVG. DEV 11.87%

$$K_p = 85.49$$

$$C_p = .99$$

$$T_s = ^\circ F + 460$$

$$P_s = P_{Bar} + (P_g \text{ (static)}) \quad (\text{a negative number})$$

$$M_s = 28.56$$

$$V_s = K_p C_p (AP) \sqrt{\frac{T_s}{P_s + M_g}}$$

Excel program is located: K:\groups\test\dept\misc\ee\calibrat\velomete

EQUIPMENT CALIBRATION RECORD
 WARNOCK HERSEY, INC.
 MIDDLETON, WISCONSIN 53562

A. IDENTIFICATION:

1. TYPE AND MODEL DESIGNATION - Dry Gas Meter Calibration
2. MANUFACTURER/SUPPLIER - ① Rockwell T-110 #26866 WHI #12
② Rockwell T-110 #26873 WHI #13
③ Rockwell T-110 #27002 WHI #14
3. SERIAL NO./WH DESIGNATION NO. _____

B. EQUIPMENT LOCATION:

1. PURPOSE & ACCURACY - ±.05 CFH
2. CALIBRATION INTERVAL - 6 months

C. CALIBRATIONS: DONE BY- _____

CALIBRATION DATE	CALIBRATION DUE NEXT	CALIBRATION AGENCY	ACCEP	CALIBRATION RESULTS ADJUSTMENTS REQUIRED
1/3/96	7/3/96	Inhouse	DS	
7/9/96	1/9/97	Inhouse	DS	
12-4-96	6-4-97	Inhouse	RA	
6-2-97	12-2-97	"	RA	
12/12/97	6/12/98	"	RA	
6/22/98	12/22/98	"	WK	
1/19/99	7/19/99	"	RA	
5/3/99	11/3/99	MG + E	-	
1/12/00	7/12/00	In-house	RA	

D. MAINTENANCE AND REPAIR:

DATE OUT OF SERVICE	DATE BACK IN SERVICE	REPAIR AGENCY	DESCRIPTION OF REPAIR OR MAINTENANCE



Interte. esting Services

Manufacturer ROCKWELL Model T110 Date 1-12-99 Page of

Job # Run Tech RA Inventory Number 3 014 1.0469

SPIROMETER (Six Month Dry Gas Meter Calibration)

Run Number	Meter Initial	Barometric Pressure	Spirometer Temperature	Vapor Press (H2O)	Meter Temperature	Meter Pressure	Measurement Inches	Spirometer Volume	Meter Final	Y
1	294.005	29.722	66	.6380	65.5	.47	23.03125	295.005	295.005	1.0230
2	295.005	29.19	65	.6160	65.5	.47	23.125	296.000	296.008	1.0269
3	296.008	29.19	66.5	.6495	65	.47	23.5625	1.0710	297.032	1.0197
4	298.083	29.19	66	.6380	65.5	.47	22.9375	1.0426	299.082	1.0195
5	299.082	29.19	66	.6380	65	.47	23.125	1.0511	300.328	1.0206
6	300.328	29.19	65	.6160	65	.47	22.875	1.0398	301.329	1.0168
7										
									AVERAGE	1.0212

SN 26866

Run Number	Meter Initial	Barometric Pressure	Spirometer Temperature	Vapor Press (H2O)	Meter Temperature	Meter Pressure	Measurement Inches	Spirometer Volume	Meter Final	Y
1	902.825	29.22	66	.6380	68	.47	23.03125	903.833	903.833	1.0198
2	903.833	29.19	65	.6160	68.5	.47	23.125	1.0511	904.848	1.0208
3	904.848	29.19	66.5	.6495	69	.47	23.5625	1.0710	905.893	1.0069
									AVERAGE	1.0157

SN 26873

Run Number	Meter Initial	Barometric Pressure	Spirometer Temperature	Vapor Press (H2O)	Meter Temperature	Meter Pressure	Measurement Inches	Spirometer Volume	Meter Final	Y
1	283.205	29.19	66	.6380	67	.47	22.9375	1.0426	284.197	1.0300
2	284.197	29.19	66	.6380	67	.47	23.125	1.0511	285.428	1.0384
3	285.428	29.19	65	.6160	67	.47	22.875	1.0398	286.4105	1.0399
									AVERAGE	1.0361

$$Y = \left[\frac{V_{SPR}}{MR} \right] \left[1 - \frac{P_{H2O}}{P_{BAR}} \right] \left[\frac{T_M + 460}{T_{SPR} + 460} \right]$$

K: groups test forms sfa&cc eval-sht testdata revsheet 26

ITS EQUIPMENT CALIBRATION RECORD

ITS# #9, 10, 11

DESCRIPTION: CO, CO₂, O₂ Analyzers

MANUFACTURER: Horiba + Beckman

SERIAL #: CO PIR-2000 #9 MODEL: CO₂ PIR-2000 #10 O₂ 755 #11
6110019 607023 1001926

EQUIPMENT LOCATION: _____

PURPOSE & ACCURACY: ± 1% of FS

CALIBRATION SPECIFICATIONS/INTERVAL: 6 mos.

CALIBRATION DATE	NEXT CALIBRATION	CALIBRATION AGENCY	CAL. BY	RESULTS/ADJUST.
7/16/99	1/16/00	In House	RA	
1/17/00	7/17/00	"	RA	

MAINTENANCE AND REPAIR:

DATE OUT OF SERVICE	DATE BACK IN SERVICE	REPAIR AGENCY	DESCRIPTION OF REPAIR

ITS Intertek Testing Services NA Inc.

Middleton, Wisconsin

CALIBRATION DATE: 1-17-00 CALIBRATED BY: RA
REVIEWED BY: [Signature]

DESCRIPTION: Gas Analyzers

Located in EE console

SERIAL NUMBER: 6110019 CO

WHI INVENTORY #009

SERIAL NUMBER: 607023 CO₂

WHI INVENTORY #010

SERIAL NUMBER: 1001926 O₂

WHI INVENTORY #011

GAS ANALYZER RESPONSE TIME

CALIBRATION GAS USED

	CO	CO ₂	O ₂
Analysis:	<u>.991</u>	<u>10.02</u>	<u>10.01</u>
Meter Reading			
Direct Connection:	<u>.98</u>	<u>9.74</u>	<u>10.08</u>
90% of Analysis:	<u>.892</u> .991 RA	<u>9.02</u>	<u>9.01</u>

- Meters set with zero gas and span gas.
- Calibration gas routed through impinger train.
- Zero gas was introduced after each time trial to return meter to zero.

CO	90% (<u>.892</u>)	Trial Time		100% (<u>.95</u>)	Trial Time	
		Trial	Time		Trial	Time
		1.	<u>5</u> sec	1.	<u>11</u> sec	
		2.	<u>5</u> sec	2.	<u>10</u> sec	
		3.	<u>5</u> sec	3.	<u>10</u> sec	
		Average	<u>5</u> sec	Average	<u>10.33</u> sec	

CO ₂	90% (<u>9.02</u>)	Trial Time		100% (<u>9.43</u>)	Trial Time	
		Trial	Time		Trial	Time
		1.	<u>5</u> sec	1.	<u>11</u> sec	
		2.	<u>5</u> sec	2.	<u>11</u> sec	
		3.	<u>6</u> sec	3.	<u>11</u> sec	
		Average	<u>5.33</u> sec	Average	<u>11</u> sec	

O ₂	90% (<u>9.01</u>)	Trial Time		100% (<u>10.16</u>)	Trial Time	
		Trial	Time		Trial	Time
		1.	<u>14</u> sec	1.	<u>30</u> sec	
		2.	<u>16</u> sec	2.	<u>30</u> sec	
		3.	<u>16</u> sec	3.	<u>32</u> sec	
		Average	<u>15.33</u> sec	Average	<u>30.67</u> sec	

ITS EQUIPMENT CALIBRATION RECORD

ITS# FE 500

DESCRIPTION: THERMOCOUPLES

MANUFACTURER: OMEGA

SERIAL #: _____ MODEL: _____

EQUIPMENT LOCATION: E+E LAB

PURPOSE & ACCURACY: _____

CALIBRATION SPECIFICATIONS/INTERVAL: BOILING WATER ICE BATH 6 MONTHS

CALIBRATION DATE	NEXT CALIBRATION	CALIBRATION AGENCY	CAL. BY	RESULTS/ADJUST.
6-4-97	12-4-97	IN HOUSE	RA	
12-12-97	6-12-98	"	RA	
6-26/98	12-26-98	"	WK	
12-11-98	6-11-99	"	RA	
6/1/99	12/1/99	"	RA	

MAINTENANCE AND REPAIR:

DATE OUT OF SERVICE	DATE BACK IN SERVICE	REPAIR AGENCY	DESCRIPTION OF REPAIR

ITS Intertek Testing Services NA Inc.

Middleton, Wisconsin

CALIBRATION DATE: 6-1-99
REVIEWED BY: [Signature]

CALIBRATED BY: RA

500
ITS # TC

ROOM TEMPERATURE 74

Thermocouple number and location	Thermocouple immersed in boiling water	Thermocouple immersed in ice bath
1) Flue Gas	212	34
2) Room Temperature	212	34
3) Dry Bulb (in tunnel)	212	34
4) Wet Bulb (in tunnel)	211	33
5) Unit Top	212	34
6) Unit Back	211	33
7) Unit Right Side	212	34
8) Unit Left Side	212	33
9) Unit Bottom	212	34
10) Catalyst Downstream	212	34
11) Catalyst Center	212	34
12)	212	34
13)	212	34
14)	212	34
15)	212	34
16)	212	34
17) DGM (in)	212	34
18) DGM (out)	212	34
19) Filter (1)	212	34
20) DGM (in)	212	34
21) DGM (out)	212	34
22) Filter (2)	212	34

ITS EQUIPMENT CALIBRATION RECORD

ITS# 8 v 259

DESCRIPTION: weigh

MANUFACTURER: Tronix

SERIAL #: ⁽⁶⁾(8)6800082 ⁽²⁵⁾(259)03082 MODEL: ⁽⁸⁾NCI 5780 ⁽²⁵⁹⁾WI 110

EQUIPMENT LOCATION: _____

PURPOSE & ACCURACY: .1 lb

CALIBRATION SPECIFICATIONS/INTERVAL: 6 Months

CALIBRATION DATE	NEXT CALIBRATION	CALIBRATION AGENCY	CAL. BY	RESULTS/ADJUST.
8-11-98	2-11-99	In-house	RA	
5-19-98	11-19-98	Cream City	-	
11-98	5-99	CREAM CITY	JEFF	
5/21/99	11/21/99	" "	CC	
11/99	5/00	Cream City	Jeff	

MAINTENANCE AND REPAIR:

DATE OUT OF SERVICE	DATE BACK IN SERVICE	REPAIR AGENCY	DESCRIPTION OF REPAIR

*6

Certificate of Calibration CREAM CITY SCALE, CO INC.

2009 S. Stoughton Rd., Madison, WI 53716 (608) 222-9427 or (888) 934-4448

CUSTOMER ITS.
ADDRESS 8431 Murphy Dr
CITY, STATE & ZIP Madison WI 53562

DATE 11/95

INDICATOR MFG.	<u>GSE</u>	CAPACITY	<u>100 Lb</u>	CLASS	<u>III</u>
MODEL	<u>450</u>	DIVISIONS	<u>.01</u>	ACCURACY	<u>1/40</u>
SERIAL NO.	<u>101722</u>	LOCATION	<u>E & E</u>	TOLERANCES USED	<u></u>
BASE MFG.	<u>NCI</u>	I.D. #	<u></u>		<u>H099</u>
MODEL	<u>3220</u>	CALIBRATION INTERVAL	<u>Semi Annual</u>		
SERIAL NO.	<u>790143</u>	NEXT CALIBRATION DUE	<u>5/00</u>		

SHIFT TEST

FLOOR SCALE

BENCH SCALE

1	2
4	3

2	3
4	

SECTION	LOAD	READING	ERROR
1	50.00	50.00	0
2	50.00	50.00	0
3	50.00	50.00	0
4	50.00	50.00	0

IS SHIFT TEST WITHIN TOLERANCE () YES () NO () ADJUSTED

INCREASING LOAD TEST

PRELIMINARY LOAD TEST

SUBSTITUTION WEIGHT	TEST WEIGHT	READING	ERROR
	5.00	5.00	0
	10.00	10.00	0
	15.00	15.00	0
	20.00	20.00	0
	25.00	25.00	0
	50.00	50.00	0
	75.00	75.00	0

FINAL LOAD TEST AFTER ADJUSTMENT

SUBSTITUTION WEIGHT	TEST WEIGHT	READING	ERROR

IS SCALE WITHIN MAINTENANCE TOLERANCE () Y () N
(if no. see final load test)


IS SCALE WITHIN ACCEPTANCE TOLERANCE () Y () N

WAS SCALE WITHIN CUSTOMERS REQUIRED ACCURACY? () Y () N

COMMENTS:

TEST WEIGHT CLASSIFICATION F
 NIST TRACEABILITY CERTIFICATE NO. W95-206
 LIST TEST WEIGHTS USED BY SERIAL NO. 675, 71

SCALES WERE CALIBRATED WITH THE CERTIFIED TEST WEIGHTS, ADJUSTMENTS TO RESTORE AND/OR MAINTAIN THE ACCURACY OF THE SCALE CONFORM TO THE TOLERANCES ESTABLISHED BY THE NATIONAL INSTITUTE OF STANDARDS & TECHNOLOGY AS SPECIFIED IN HANDBOOK 44.

TECHNICIAN 

#25

Certificate of Calibration CREAM CITY SCALE, CO INC.

2009 S. Stoughton Rd., Madison, WI 53716 (608) 222-9427 or (888) 934-4448

CUSTOMER J.T.S. DATE 11/99
ADDRESS 8431 Murphy DR
CITY, STATE & ZIP Middleton WI 53562

INDICATOR MFG. <u>Weightronix</u>	CAPACITY <u>980#</u>	CLASS <u>TTL</u>
MODEL <u>WI 110</u>	DIVISIONS <u>.1</u>	ACCURACY <u>1%</u>
SERIAL NO. <u>30821</u>	LOCATION <u>E+E</u>	TOLERANCES USED <u></u>
BASE MFG. <u>Toledo</u>	I.D. # <u>259</u>	<u>HB 40</u>
MODEL <u>Durmount</u>	CALIBRATION INTERVAL <u>Semi Annual</u>	
SERIAL NO. <u>N/A</u>	NEXT CALIBRATION DUE <u>5/00</u>	

SHIFT TEST

FLOOR SCALE

BENCH SCALE

1	2
4	3

2	
1	3
4	

SECTION	LOAD	READING	ERROR
1	50.0	50.0	0
2	50.0	50.0	0
3	50.0	50.0	0
4	50.0	50.0	0

IS SHIFT TEST WITHIN TOLERANCE () YES () NO () ADJUSTED

INCREASING LOAD TEST

PRELIMINARY LOAD TEST

SUBSTITUTION WEIGHT	TEST WEIGHT	READING	ERROR
	50.0	50.0	0
	100.0	100.0	0
	200.0	200.0	0
	400.0	400.0	0
	600.0	600.0	0
	800.0	800.0	0
	900.0	900.0	0

FINAL LOAD TEST AFTER ADJUSTMENT

SUBSTITUTION WEIGHT	TEST WEIGHT	READING	ERROR

IS SCALE WITHIN MAINTENANCE TOLERANCE () Y () N
(if no, see final load test)

IS SCALE WITHIN ACCEPTANCE TOLERANCE () Y () N

WAS SCALE WITHIN CUSTOMERS REQUIRED ACCURACY? () Y () N

COMMENTS:

TEST WEIGHT CLASSIFICATION F
NIST TRACEABILITY CERTIFICATE NO. 4198-206
LIST TEST WEIGHTS USED BY SERIAL NO. 71, 72, 73, 74, 75, 76, 77, 78, m 689

SCALES WERE CALIBRATED WITH THE CERTIFIED TEST WEIGHTS, ADJUSTMENTS TO RESTORE AND/OR MAINTAIN THE ACCURACY OF THE SCALE CONFORM TO THE TOLERANCES ESTABLISHED BY THE NATIONAL INSTITUTE OF STANDARDS & TECHNOLOGY AS SPECIFIED IN HANDBOOK 44.




TECHNICIAN [Signature]

APPENDIX F


Specifications for Morsø 1410 N

Dimensions:	Height: 700 mm, Width: 390 mm, Depth: 395 mm
Cast items:	GG 15-20, thickness 5 mm
Pipe connection:	Rear or top, Ø 120 mm
Brick:	Refractory chamotte bricks, thickness 25 mm
Glass:	5 mm high-temperature resistant, laid in 2 mm ceramic paper
Glass frame:	1.5 mm stainless steel
Sealing strip:	5 mm and 8 mm ceramic glass cord
Internal plate sections:	3 mm high-temperature resistant plates
Ash pan:	1 mm SPD plate
Rear convection plate:	1 mm SPD plate
Heat shield:	0.5 mm galvanised plate
Spacing bushes:	Ø 20 x 1 mm galvanised pipe
Screws:	M6, no special strength requirements
Surface:	Coated with senotherm
Accessories:	Poker, ceramic sealing cord for assembling pipe sections, and Morsø glove

26th January 1999 - Sign.: Rita Svenningsen
Morsø Jernstøberi A/S - DK-7900 Nykøbing Mors






 <p>LEVERANDØRTIL DET KGL. DANSKE HOF</p> <p>MORSØ</p> <p>ANTIKBESKÆFT H. A. CHRISTENSEN & CO. DK-7000 FREDERIKSBORG TEL. 9713150</p>	<p>NORSØ 1410/1415</p>	
	<p>DATE: 27/10-1997</p> <p>MÅL: 1:5</p> <p>TEGNINGSNR.: 1400-180-3</p>	<p>RENDERET</p> <p>MODELNR.</p>




Tolerance: + 0 %
- 2 %
Matr. Ildfast sten

Rev.	Revision	Sign.	Dato	Titel:	Sign.:	Dato:
b	Mål ændret	RSV	11.02.98	Sidesten	RS	980205
c	Mål ændret	RSV	17.04.98	Morsø 1440 N	Tegn.form.: A4	Målforshold 1:2.5
				Filnavn: 1400-189	Varenummer: 79094700	
				MORSØ Jernstøberi A/S	Tegningsnummer: 1400-189 c	



Snit A-A




Snit B-B

Generelle tolerancer $\pm 0.5\text{mm}$

Matr.: Mo 3 (Rustfast stål)

Revision	Sign.	Dato	Titel:		Sign.	Dato:
Ændret	RS	09.02.98	Røgledeplade stål		RS	09.02.98
Tilføjet mål	RS	10.02.98	Morsø 1440 N		Tegn.form.:	Målførhold
Tilføjet huller+mål	RS	13.02.98	Filnavn: 1400-187		A3	1:2.5
Ændret mål+radie	RS	18.02.98	Varenummer: 71141361		Tegningsnummer: 1400-187-3	
			MORSØ <small>Jernstøberi A/S</small>			



	Høbbø - 4410 A (S) - 100000	15. ANS. 97 1987 22. 05. 97 1987 22. 05. 97 1987 22. 05. 97	1987 22. 05. 97 1987 22. 05. 97 1987 22. 05. 97
--	--------------------------------	--	---

Flue outlet backside
 Hole in Gackside

APPENDIX G


morsø

By appointment to  the Royal Danish Court

Installation and Operating Instructions

1410 Squirrel

For use in North America



Read this entire manual before you install and use your new room heater. If this room heater is not properly installed, a house fire may result. To reduce the risk of fire, follow the installation instructions. Failure to follow instructions may result in property damage, bodily injury, or even death.

Contact local building officials about restrictions and installation inspection requirements in your area.

Save these instructions

MORSØ JERNSTØBERI A/S · DK-7900 NYKØBING MORS
E-Mail: stoves@morsoe.com · Website: www.morsoe.com

Distributed by: HEARTHLINK INTERNATIONAL
9 Maple St. - Randolph, Vermont - 05060 - USA

We congratulate you on your choice of a Morsø stove. Morsø has been producing some of the world's best stoves since 1853. If you follow this installation- and operating instruction carefully, we can assure you many years of warmth and pleasure.

Optional Accessories

A wide range of accessories (such as handling gloves, fireside tools, glass cleaner and heatproof paint) are available for use with your Morsø stove. They help with day-to-day running and maintenance. Contact your Morsø dealer for more information.

The Morsø 1410 squirrel meets the U.S. Environmental Protection Agency's emission limits for wood heaters sold on or after July 1, 1990



The Morsø 1410 squirrel has been tested by Intertek Testing Services and is listed by Warnock Hersey, Inc. The test standards are ANSI/UL-1482 for the United States and ULCS627 for Canada.

The stove is listed for burning wood only. Do not burn other fuels.

Under specific test conditions this heater has been shown to deliver heat at rates ranging from 11,000 to 25,000 Btu's.

CONTENTS:

1.0	Installation of your Morsø stove	
1.1	Checking loose parts in the stove	4
1.2	The chimney / flue system	4
1.3	Flue Connection	5
1.4	Connection to existing chimney	6
1.5	Positioning the stove	8
2.0	Operation	
2.1	Before you start firing	10
2.2	Lighting and loading intervals	11
3.0	Maintenance	
3.1	Exterior maintenance	12
3.2	Internal maintenance	12
3.3	Cleaning the Stove and the Flue	14
3.4	Leaving the stove for extended periods	16
3.5	Parts diagram	17
3.6	Parts list	18

1.0 Installation of your Morsø stove

Installation of woodburning stoves must be safe and legal.

If your Morsø stove is not installed correctly, it may cause a house fire. To reduce the risk of fire, the installation instructions must be followed carefully. Contact the local building officials about restrictions and installation inspection in your area.

Before you start installing your stove, make sure that:

- The stove and chimney connection are placed far enough from combustible materials to meet all clearance requirements.
 - The floor protection must be adequate and must be made correctly according to the requirements.
- All necessary approvals are needed from the local building officials.

The data plate, which is located on the back of the stove, provides information regarding safety testing information, name of certified testing laboratory, and installation requirements.

Installation requirements vary in different districts, and the local building officials have the final authorization to approve your installation. You should discuss the installation with them before beginning. Please ask your dealer for further information.

Do not connect to any air distribution duct or system.

Important: If the installation instructions are not followed carefully, it may cause dangerous situations like chimney - and house fires. Follow the instructions carefully and do not deviate from them as it may cause injuries to people or property.

1.1 Checking loose parts in the stove

After unpacking, check that the center grate (in the centre of the fire bed) and the fire bricks are firmly in position and have not shifted in transit. Check also that the air control works freely.

Standard Accessories

Poker, ceramic flue connection gasket and riddling tool are standard accessories, and can usually be found in the ashpan or firebox area.

1.2 The chimney / flue system

Note that the flue system must be independently secured and must not rely on the stove for support.

The stove must not be connected to a chimney flue serving any other appliance. (Several flues may run up a single chimney stack; use one flueway per appliance).

Use a residential type masonry or listed type HT factory-built chimney.


High Temperature (H.T.) Chimney Standard UL-103-1985 (2100° F.) for the USA, and High Temperature (650°C) Standard UL-C S-629 for Canada.

The internal dimensions of the chimney connector and chimney must not be less than 6 inches diameter (or equivalent cross section), and should not be significantly larger than this. Too large a section will tend to allow the flue gases to cool excessively, causing sluggishness or unpredictability in the stove's performance.

The length of the chimney system should be at least 16 feet above the stove in normal domestic situations, measured from the flue collar to the top of the chimney.

Local conditions like for example - roof constructions, large trees nearby and high altitude, may influence the chimney draft and height. Therefore, contact the local professional chimney sweep or your Morsø dealer.

Typical Factory-Built or Masonry Chimney Installations



1.5 Positioning the stove


Distance to walls and lintel

When the stove is positioned near *combustible* materials, observe all current local and national building regulations with regards to clearances. Whatever regulations apply to your area, do not in any case install the stove within 8 inches of combustible materials around the sides or 16 inches above the top of the stove. These distances may need to be increased if the materials are sensitive to heat. Note also that wall paper and other decorative materials may become detached with the effects of heat and care should be taken to ensure that they do not fall towards the stove in such an event.


When the stove is positioned near *non-combustible* materials, a gap of 4 inches or more is recommended for cleaning purposes and to ensure that heat circulates around the stove and out into the room.

Clearance chart:


With double-wall or single-wall chimney connector				
	Unit to backwall	Unit to sidewall	Connector to wall	Unit corner to wall
Morsø 1410 double-wall	6" (155 mm)	20" (510 mm)		
Morsø 1410 single-wall	16" (405 mm)	20" (510 mm)	18" (460 mm)	
Morsø 1410 corner				14" (355 mm)




Double-wall chimney connector



Single-wall chimney connector



Corner




Side

On the floor

If the stove is to be placed on a combustible floor, a solid, non-combustible layer should cover the floor beneath the stove. This layer should cover an area of at least 16 inches in front of the stove door and at least 8 inches either side of the opening and 6" to the rear. You must ensure that the floor in this area can hold the weight of the stove comfortably.

In Canada non-combustible floor protector is required under the stove as well. The floor protector must extend 18 inches (460mm) to the front and 6 inches (155mm) from the sides and rear.



	U.S.	Canada
A.	41"	41" (1045 mm)
B.	43"	45" (1145 mm)
C.	6"	6" (155 mm)
D.	8"	6" (155 mm)
E.	16"	18" (460 mm)

Distance to furniture

The recommended minimum distance from stove to furniture is 30 inches. Note that some furniture is more easily affected by heat and may need to be moved to a greater distance. This is your responsibility.

In addition other combustible materials, away from the stove. In general, a distance of 30 inches must be maintained between the stove and moveable combustible item such as drying clothes, newspapers, firewood etc.

Note:

Acid Protection

If acid-washing the masonry around the stove, protect the stove surface with an acid-proof cover

Fresh Air Inlet

Unless there is deemed to be sufficient ambient leakage of air into the room via doorways, windows and the like, a dedicated fresh air inlet will be needed. This inlet should have 2 square inches (1250 square mm) of free air space. This is particularly important where the room is well sealed, or where an extractor hood or ventilation system disturbs the natural air pressure. Such an inlet should not be on a wall that is usually subject to negative pressure from normal wind pattern. Avoid placing the inlet directly across the room from the stove, thus causing a cold air draft.

2.0 Operation

2.1 Before you start firing

For Use with Solid Wood Fuel Only. Do Not Overfire, If Heater or Chimney Connector Glows You Are Overfiring. Inspect and Clean Chimney Frequently. Under Certain Conditions of use creosote buildup may occur rapidly. Because of risk of smoke and flame spillage, operate only with door fully closed.

Caution:

Hot while in operation. Keep children, clothing and furniture away. Contact may cause skin burns.

Do not use chemicals or fluids to start the fire.

Do not burn garbage or flammable fluids.

Choosing your fuel

All types of natural wood can be burned on your stove, but they must be well-seasoned and dry. Once the wood is cut to length, it should be split down middle - to suit the dimensions given below - to allow moisture to evaporate.

Cut the wood to a length of 10 inches (25 cm) and approx. 3 to 3,5 inches (7-8 cm) in section. If you can weigh your wood, aim for around 0,7 kg.

The maximum moisture content of the wood should be around 20%.

Store the logs under cover in a location where fresh air can move through the stack. Some soft woods may take as little as one good summer to season, where some harder woods may take a couple of years or more. Well seasoned wood will be remarkably light to hold and will probably have radial cracking at the ends. If your wood spits or sizzles when burnt, and your stove's door glass persistently mists up, your wood is not properly seasoned.

Never use drift wood (from the sea), whose salt content may cause corrosion, nor construction wood that may have been impregnated with chemicals.

Firing

The initial fire should be small, so that the stove paint can cure and the main plates of the stove can settle into position. Some fumes will be given off by the paint. Ventilate the room during this phase.

The setting of the valve, lighting techniques and loading intervals will depend on chimney draft, the fuel used, the heat required and so on. Some basic techniques are outlined below.

In principle

Your stove has two air supplies:

Primary air is controlled by the upper air controller of the door. The air eventually washes at high speed down the back face of the door glass. This super-heated air helps with the combustion of volatile gases produced by the fire.

Secondary air is supplied to the top of the fire through two rows of holes in the steel baffle. This effectively burns off other residual gases, making for very clean emissions. This air supply is

constant and cannot be varied.

The lower air controller on the door is fixed, and only for decoration purposes.

2.2 Lighting and loading intervals

When first lighting the stove, a large volume of air is needed. When the stove is cold, you should leave the door open an inch or two for the first few minutes and open the primary air supply completely. While the door is open, do not leave the stove unattended.

To form a reasonable bed of ash on the floor of the stove, you should use 5-6 inches thickness (2-4 pound) of dry kindling at the initial lighting. Always maintain a 1-1,5 inch (2-3 cm) layer of ash on the floor of the combustion chamber at all other times.

Step-by-step procedure

1. The air supply must be fully open. Maximum 4 turns.
2. Light the fire. An ember bed will quickly be formed by lighting with firelighters, morsos kindling bags or 7-10 pieces of twisted paper under the dry kindling wood (see above).
3. After lighting, partially close the door, leaving it open an inch or two to allow in plenty of combustion air.
4. When the chimney is warmed through after 5-10 minutes, the door should be closed. A suitable ember bed will be formed after a further 15-20 minutes.
5. When ready to reload, use a poker to spread the ember across the firebox floor, bringing plenty towards the front of the stove.
6. Lay three pieces of wood (see dimensions above) onto the embers. Leave half an inch (1 cm) or more between each piece. Place the ends of your logs towards the opening, but not too close to the front.



7. Close the door. Leave the primary air supply fully open.
8. After a few minutes, and adjust the primary air supply to suit your heating requirements.
9. Anticipate each refueling, remembering to add a modest layer of wood while there are still plenty of live embers. Repeat steps 5-8.

Do not for any reason attempt to increase the firing of your heater by altering the air control adjustment range outlined in these directions.

Warning: Fireplace stoves must never be left unattended with doors open.

If door are left partly open, gas and flame may be drawn out of the fireplace stove opening, creating risks from both fire and smoke.

DO NOT OVERFIRE THIS HEATER. Overfiring may cause a house fire, or can result in permanent damage to the stove. If any part of the stove glows, you are overfiring.

Draft conditions

If smoke or fumes come out of your stove when lighting up and reloading, or if the fire simply will not respond, a poor draft is almost certainly to blame. (In a very few cases, there may be insufficient fresh air getting into the room - see installation advice above). Take advice from your stove supplier on how best to upgrade your flue system to improve draft.

Rules of woodburning

If you want less heat, put fewer logs on the stove and reduce the amount of air. It is still important to maintain a good layer of embers.

Less heat - less wood - less air

Greater heat - more wood - more air

Soot deposits will settle on the glass if the stove is run too slowly or if your wood is not well seasoned.

3.0 MAINTENANCE

When performing maintenance on your stove always protect yourself, using safety goggles or gloves

3.1 Exterior Maintenance

The stove surface is painted with heat-resistant Senotherm paint. It is best kept clean by vacuuming with a soft brush attachment or by wiping with a lint-free cloth. Over a period of time, the painted surface may become slightly grey. A can of Morsø touch-up spray paint should be available from your stove supplier. This can be applied - in accordance with the instructions - in just a few minutes. When first firing after touching up, the stove will give off a slight smell as the paint cures. Make sure to ventilate the room well during this phase.

3.2 Internal maintenance

Glass

If the stove is generally run at the correct temperatures, there should be little or no dirt on the glass. If dirt does settle during lighting, most will burn off as temperatures increase. For heavier deposits that will not burn off, use morsø glass cleaner, applied when the glass is cold, in accordance with the instructions.

Reasons for dirty glass

- Fuel too wet
- Logs too large or not split
- Combustion temperatures too low

Replace broken glass immediately.


Do not operate your stove if the glass in the door is damaged.

If you need to replace the glass, it should be replaced with the high temperature ceramic glass supplied by Morsø, contact your Morsø dealer.

Installing the glass

Never install the glass when the stove is in function.

1. Lift the door off its hinges and place face-down on a sheet of cardboards or other non-abrasive fabric.



2. Unscrew the five bolts that secure the glass. (In the event that a bolt sheers off when being unscrewed, remove the remaining body of the bolt by drilling down its centre with 1/8 inch high speed steel drill bit. Smaller drill bits may be successful, but do not use a larger bit. Make sure the bit stays away from the edges of the bolt - this may damage the thread in the cast iron).

3. Remove the old ceramic gaskets and clean up the surface underneath with wire wool or emery paper to remove loose particles.

4. Place the new gasket material in position around the perimeter of the window area, making sure to pinch them to the length in such a way that they make a continuous seal. Leave no gaps.

5. Place the new glass in position on the strips and screw home the fresh bolts and fitting by hand.

6. Finally, give each of the bolts an extra half turn or so. The glass should held tight enough that cleaning will not dislodge it. Do not over-tighten the bolts as this may put excessive pressure on the glass, resulting in cracking - important!

To reduce the risk of breaking the glass, avoid striking the glass or slamming the door.

Internal service parts

The flame-path equipment - consisting of the ashpan, grate, firebricks, glass, baffle and flue collar - are subject to the extremes of heat produced by the fire. From time to time, one or other of these parts may need replacing as a matter of routine maintenance.

NOTE: The flame-path equipment, the ceramic rope and the paint finish are not covered by guarantee.

All of these service parts can be bought from your morskø dealer, and we recommend that damaged parts are replaced as soon as possible to avoid collateral damage.

The grate may be replaced by lifting it by its left hand edge and twisting it backwards. Dislocate the riddling arm from the grate by feel from beneath the floor of the firebox. If you find this difficult for any reason, raising the rectangular grate surround casting may help.

Should the baffle be distorted by an overfire, the stove will still function, although its efficiency may be compromised. Replace it as soon as possible. The rear casing is removed (four bolts). Remove these and withdraw the baffle from the firebox (this may be easier if the firebricks are first removed).

Before replacing the baffle, scrape out the old fire furnace and replace with new to make an effective seal.

Reasons for fast internal wear and tear

Persistent heavy firing

Soot and ashes left to accumulate

Ceramic Gasket

The gasket around the perimeter of the door may harden over a period of time. It should be replaced if it becomes difficult to close the door or if air starts to leak in around the perimeter of the door, causing the fire to become a little less controllable. A morskø rope gasket kit is available from your stove supplier.

3.3 Cleaning the Stove and the Flue

Check for soot above the baffle plate and around the flue outlet every month or so to start with. If the stove suddenly becomes sluggish, check for a soot fall around the flue collar or in the flue/chimney. - at least once a year. Inspect every month.

Clean the flue/chimney - all the way from the stove to the flue terminal point above the house.

A good routine is to clean the flue after each heating season in any case, although inspect prior to the season to ensure that bird's nests or other blockages have not occurred during the off season.

Ash disposal

Empty the ashpan on a daily basis or as needed. Ash allowed to build up towards the underside of the grate will trap heat and could cause premature failure of the grate.

Empty the ashpan according to this procedure:

When the door is closed, the grate can be operated by means of the riddling bar. Open the front door, and use a shovel or poker to stir excess ash through the ash slots in the grate down into the ash pan. Remove the ash pan, making sure to keep it level.

Dispose the ash in a metal container with a tight fitting lid.

The closed container of ashes should be placed on a noncombustible floor or on the ground, well away from all combustible materials, pending final disposal. If the ashes are disposed of by burial in soil or otherwise locally dispersed, they should be retained in the closed container until all cinders have thoroughly cooled.

Return the ash pan to its original position in the stove, and close.

Caution:

Never empty a stove in operation.

Never use your household or shop vacuum cleaner to remove ash from the stove; always remove and dispose of the ash properly.

Creosote - formation and need for removal

When wood is burned slowly, it produces tar and other organic vapors, which combine with expelled moisture to form creosote. The creosote vapors condense in the relatively cool chimney flue of a slow-burning fire. As a result, creosote residue accumulates on the flue lining. When ignited this creosote makes an extremely hot fire. When burning wood, inspect the chimney connector periodically to determine if a creosote buildup has occurred.

Chimney sweeping

Inspect the system regularly during the heating season as part of a regular maintenance schedule. To inspect the chimney, let the stove cool completely. Then, using a mirror, sight up through the flue collar into the chimney flue. If you cannot inspect the flue system in this fashion, the stove must be disconnected to provide better viewing access.

Clean the chimney using a brush the same size and shape as the flue liner. Run the brush up and down the liner, causing any deposits to fall to the bottom of the chimney where they can be removed through the clean-out door.

Clean the chimney connector disconnecting the sections, taking them outside, and removing any deposits with a stiff wire brush. Reinstall the connector sections after cleaning, being sure to secure the joints between individual sections with sheet metal screws.

If you cannot inspect or clean the chimney yourself, contact your local Morskø Dealer or a professional chimney sweep.

If you do experience a chimney fire, act promptly and:
 Close the air control.
 Get everyone out of the house.
 Call the Fire Department.

Annual maintenance

Before the heating season, perform a thorough cleaning, inspection and repair:
 Thoroughly clean the chimney and chimney connector.
 Inspect the chimney for damage and deterioration. Replace weak sections of prefabricated chimney. Have a mason make repairs to a masonry chimney.
 Inspect the chimney connector and replace any damaged sections.
 Check gasketing for wear or compression, and replace if necessary.
 Check the glass for cracking; replace if needed.
 Check door and handles for tightness. Adjust if needed.

3.4 Leaving the stove for extended periods

Important:

If the stove is to be left unused for any period of time, clean it out thoroughly and leave the spinner slightly open to allow airflow. Make sure that the flue does not allow rainwater to come anywhere near the stove; install a chimney cap, but do not block off the flue completely. These measures should ensure there is a slight movement of air through the stove, and that the body of the stove remains dry, right into the corners.


Any ash left within an unfired stove can attract moisture like blotting paper. If moisture is allowed to settle within the stove, rust will form. Rust expands as it takes a grip. This can lead to undue pressure on the stove joints, and this in turn may result in damage to the stove.

NOTE: It is best to thoroughly clean the stove after the heating season has concluded. Adding a desiccant, such as kitty litter, into the ash pan helps absorb moisture during the summer months. Be sure to remove this prior to the heating season.

Thank you for buying a morsø stove.

We hope you have many years of carefree warmth in its company. Some initial experimentation with loading and running techniques will decide your normal routine. If you have any problems after this short learning phase, please refer to your stove dealer. Should they be unable to help for any reason, please contact us in writing at the address on the front of this publication.

3.5 Parts diagram for the model Morsø 1410 squirrel



3.6 Parts list for the model Morsø 1410 squirrel

1	Rear plate, inside	34145100
2	Base plate	44140100
3	Side plate w. squirrel	44140600
4	Top plate	44140700
5	Cover	44141021
6	Front grate	44141400
7	Attachment for front grate	44141600
8	Flue collar	44141700
9	Front frame	44142200
10	Door	44142321
11	Draft reducer	44142800
12	Intermediate frame	44144900
13	Rear plate, outside	44145000
14	Baffle plate, cast iron	44145200
15	Frame for riddling grate	44203100
16	Leg	44203221
17	Riddling grate	44203300
18	Air valve	44241421
19	Fitting w. thread for flue collar	44256700
20	Fitting without thread f. cover	44256800
21	Handle for riddling grate	44262021
22	Distance tube	540614
23	Poker	541075
24	Hinge pin	541403
25	Ash tray	541405
26	Convection rear plate	541425
27	Radiant shielding, bottom	541426
28	Distance tube	541439
29	Riddling bar	541442
30	Radiant shielding, rear	541446
31	Distance tube	542635
32	Baffle plate, stainless	71141361
33	6x12 black steel set screw	731612
34	6x16 black steel set screw	731616
35	6x25 black steel set screw	731625
36	6x40 black steel set screw	731640
37	8x25 black steel set screw	731825
38	8x30 black steel set screw	731830
39	6 mm black washer	736106
40	5x8 bolt	742508
41	6x10 bolt	74361000
42	6x25 bolt	743625
43	6 mm brass washer	746006
44	6 mm clip pulley	746206
45	Knob for riddling grate	752619
46	Ceramic glass	790724
47	Tightening tape	79074400
48	Stone	79094700
49	Locking device	79127200
50	5x30 cotter pin	79186300
51	6x32 cotter pin	791868
52	6x26 cotter pin	791869
53	6 mm air slider washer	791891
54	8 mm washer	79189500
55	Glass fitting	79127300
56	Handle	71145700
57	Adaptor	71145800
58	3.5x9.5 self tapping schrow	791835
59	6x20 black steel set screw	731620
60	Glas fitting	71145900
61	Hanging for handle	71146000



MORSØ JERNSTØBERI A/S

BY APPOINTMENT TO THE ROYAL DANISH COURT

DK-7900 NYKØBING MORS

Rick Armstrong
Intertek Testing Services
8431 Murphy Drive
Middleton, Wisconsin 53562

Subject: Air control settings for Model 1410 Wood-burning stove.

Dear Mr. Armstrong

The Squirrel wood heater scheduled to be tested in your facility for EPA particulate emissions can be operated in the following manner to obtain results in each category.

Burn rate category	Primary air setting	Time at full open setting
1	1 turn	5 min
2	1 ¼ turns	5 min
3	2 ½ turns	5 min
4	full open	n/a

Door open time is at the discretion of the tester.

Regards,

Karsten Aagaard
Morsø Stoves

Address:
Morsø Jernstøberi A/S
Furvej 6
DK-7900 Nykøbing Mors
Phone: Salesdept. +45 96 69 19 00
Accounts: -45 96 69 19 20
Production: -45 96 69 19 30

CVR no 15 31 42 85
VAT no DK 17 00 25 37 (export only)
PBS nr. 00 18 27 98 (only for DK)
E-mail Stoves@morsoe.com
Homepage www.morsoe.com
Fax -45 97 72 21 69

Bank
DKK Giro 3 35 11 57
DKK Den Danske Bank, Thisted - acc. no. 4784 - 421465
DKK Morsø Spenkehaase, Nykøbing Mors - acc. no. 8100 - 1021106618
DEM Den Danske Bank, Hamburg - KTO. Nr. 32381009
(BLZ 203 205 00)
GBP Den Danske Bank London - acc. no. 69639

APPENDIX H

1. TUNNEL FLOW RATE

Tunnel flow rates are determined using the velocity pressure measurement made by a standard Pitot tube. The Pitot tube is located at the center of the dilution tunnel. Three x/y axis traverses were used to determine the relationship between the center velocity pressure and the average obtained by traversing. This procedure was carried out in accordance with EPA Method 2.

Velocity pressure and tunnel temperature data are used to calculate tunnel velocity via EPA Method 2, equation 2-9 as follows:

$$T_v = K_p * C_p * \sqrt{\Delta P} * \sqrt{\frac{T_s}{P_s * M_s}}$$

- Where:
- K_p = 85.49 (English units constant for ft/sec.)
 - F_p = Pitot tube center point coefficient determined from traverses
 - C_p = .99 Coefficient for standard pitot tube
 - ΔP = Pitot tube velocity pressure (in. w.c.)
 - T_s = Absolute tunnel temperature (1R)
 - P_s = Absolute tunnel pressure (in. Hg)
 - M_s = Mole. Wt. of tunnel gas stream (lb./lb.-mole, wet basis) = 29 * (1-.04) + 18 * .04 = 28.56
 - T_v = Tunnel velocity (ft./sec.)

Tunnel flow is calculated by multiplying the average velocity as calculated by the above formula by the following equation (adaptation of EPA Method 2, formula 2-10).

$$T_f = \bar{T}_v * 60 * 0.1961 * \frac{528}{TT_{ave}} * \frac{PS}{29.92} * 1 - .04$$

Where:

- \bar{T}_v = Average tunnel velocity (ft/sec.)
- 0.1961 = Tunnel cross sectional area (ft²)
- T_f = Tunnel flow rate (SCFM)
- TT_{ave} = Average tunnel temp. (1R)
- PS = Average barometric pressure during test.
- 60 = sec. to min. conversion
- 0.04 = Assumed tunnel moisture content (4% by Vol.)

2. EMISSIONS RATE CALCULATION

Emissions rates are calculated from the total weight gain of the probe and first and second filters of each sampling system as follows:

$$ER = \left(\frac{T_f * Wt.Gain * 60}{vol.sampled} \right)^{0.83} * 1.82$$

Where: ER = Emissions rate (grams/hour OM7 equivalent)
Vol. Samp. = Total volume sampled (SCFM, Dry)
Wt. Gain = Total weight gain for filter system (grams)
T_f = Tunnel flow rate (SCFM, Dry)

3. CORRECTIONS TO STANDARD CONDITIONS

The tunnel flow rate is corrected to standard conditions through the EPA Method 2 formulae. The volume sampled is measured by dry gas meters and must be corrected for meter temperature and ambient barometric pressure. The inlet and outlet temperatures of each dry gas meter are measured and recorded at 10-minute intervals during the test. The ambient barometric pressure is recorded at the beginning and end of each test.

The following formula is used to correct the total volume as measured by the dry gas meter to total volume at standard conditions (681F, 29.92 in. Hg):

$$VOL_{std} = VOL_m * \frac{PS}{29.92} * \frac{528}{AMT} * Y$$

Where: VOL_{std} = Total volume in Standard Cubic Feet
VOL_m = Total volume as measured by dry gas meter.
PS = Average barometric pressure
AMT = Average meter temperature (1R)
Y = Dry gas meter calibration factor

EXAMPLE CALCULATIONS

1. TUNNEL VELOCITY

INPUTS: $P = .038$ in. w.c.
 $T_s = 1001$ F
 $P_s = 29.3$ in. Hg.
 $M_s = 28.56$ lb./lb.-mole
 $C_p = .99$
 $F_p = .945$

$$T_v = 85.49 * .99 * .945 * \sqrt{.038} * \sqrt{\frac{560}{29.3 * 28.56}} = 12.754$$

2. TUNNEL FLOW RATE

INPUTS: $T_v = 12.754$ ft./sec.
 $TT_{ave} = 5601$ R
 $PS = 29.3$ in. Hg.

$$T_f = 12.754 * 60 * 0.1961 * \frac{528}{560} * \frac{29.3}{29.92} * (1 - .04) = 133.0 \text{ SCFM}$$

3. EMISSIONS RATE

INPUTS: $T_f = 133.0$ SCFM
Wt. Gain = .0200 grams
Vol. Samp. = 100 Std. cubic feet

$$ER = \left(\frac{133 * .0200 * 60}{100} \right)_{83} * 1.82 = 2.68 \text{ grams / hour}$$

4. VOLUME CORRECTION FOR DRY GAS METERS

INPUTS: $VOL_m = 104.479$ (Metered Feet³)
 $PS = 29.3$ (Average baro. pressure)
 $AMT = 801F$ (Ave. meter temp.) = 5401R
 $Y = .9996$ (Meter cal. factor)

$$VOL_{std} = 104.479 * \frac{29.3}{29.92} * \frac{528}{540} * .9996 = 100.00 \text{ Standard Ft}^3$$

APPENDIX I

Warnock Hersey Efficiency Test Report

Manufacturer:	Morso					
Model:	1410					
Date:	02/03/00					
Run:	1					
Control #:	31218					
Test Duration:	143					
	Start	End				
Barometer (in.Hg):	28.73	28.78				
Wet Bulb (F):	56	59				
Dry Bulb (F):	73	79				
Humidity (%):	33	34				
Average Stove Temperature:	#DIV/0!					
Moisture content of wood (wet basis):	18.05					
	Average	1.8513	9.8763	9.2919	198.625 74.75	
Elapsed Time	Weight Remaining	CO	CO ₂	O ₂	Flue Gas	Room Temp
0	5.10	1.75	7.81	11.51	224	73
10	4.20	1.41	9.99	10.24	251	74
20	3.50	1.26	12.52	6.38	257	75
30	2.70	0.38	16.18	3.84	288	75
40	1.90	1.63	18.36	1.53	305	75
50	1.10	1.43	16.93	2.75	288	76
60	0.70	0.49	12.52	7.10	230	76
70	0.60	1.73	9.01	10.12	187	75
80	0.50	2.60	6.90	11.60	167	74
90	0.40	3.00	7.45	10.83	155	75
100	0.30	2.78	7.40	10.97	147	75
110	0.20	2.72	7.22	11.23	140	75
120	0.20	2.73	6.93	11.57	135	75
130	0.10	1.50	4.86	15.03	147	75
140	0.10	2.11	7.12	11.81	129	74
143	0.00	2.10	6.82	12.16	128	74

Overall Heating Efficiency:	70.61%				
Combustion Efficiency:	81.72%				
Heat Transfer Efficiency:	86.41%				
Heat Output:	11113	BTU/Hr	11715		
Heat Input:	15738	BTU/Hr	16591		
Burn Duration:	2.38	Hours			
Burn Rate:	1.75	Lb/Hr	0.796		
Stack Temp:	198.6	Deg.F	92.6		
	-0.00249	0.184107	#DIV/0!	#DIV/0!	3.298515
Comb %	Combust Eff %	Heat Transfer	Net Eff	air Fuel	
0.45	82.2%	21.2%	17.4%	7	
2.86	57.2%	52.7%	30.2%	6	
1.21	80.4%	72.6%	58.4%	6	
1.76	81.9%	79.3%	64.9%	5	
1.46	84.0%	84.5%	71.0%	5	
-0.13	96.8%	89.4%	86.5%	8	
-1.13	115.5%	91.1%	105.2%	14	
-0.83	105.4%	91.5%	96.5%	17	
-0.98	103.4%	91.3%	94.4%	21	
-0.91	99.1%	92.7%	91.9%	20	
-0.95	101.4%	93.3%	94.6%	22	
-0.87	100.1%	94.0%	94.0%	23	
-0.80	98.5%	94.1%	92.7%	24	
-0.03	85.6%	93.8%	80.3%	35	
-0.71	100.9%	94.9%	91.6%	26	
-0.63	99.0%	95.3%	94.3%	28	

Warnock Hersey Efficiency Test Report

Manufacturer:	Morso					
Model:	1410					
Date:	02/04/00					
Run:	2					
Control #:	31218					
Test Duration:	117					
	Start	End				
Barometer (in.Hg):	29.22	29.28				
Wet Bulb (F):	56	58				
Dry Bulb (F):	72	78				
Humidity (%):	35	28				
Average Stove Temperature:	#DIV/0!					
Moisture content of wood (wet basis):	18.82					
Average:	1.846	11.3	8.112	229.076923	74.46	
Elapsed Time	Weight Remaining	CO	CO ₂	O ₂	Flue Gas	Room Temp
0	5.22	1.40	8.63	10.80	280	73
10	3.80	1.58	14.91	4.48	335	74
20	2.90	1.36	18.65	2.08	307	74
30	2.00	0.85	18.48	1.91	296	74
40	1.30	1.53	18.95	1.11	289	75
50	0.70	0.38	13.89	6.69	255	76
60	0.60	2.24	8.74	10.13	214	76
70	0.50	2.55	8.56	10.12	191	75
80	0.40	2.46	7.96	10.83	177	74
90	0.30	2.58	7.72	10.97	168	74
100	0.20	2.48	7.20	11.64	160	74
110	0.10	2.32	6.69	12.24	155	75
117	0.00	2.29	6.47	12.46	151	74

Overall Heating Efficiency:			65.37%		
Combustion Efficiency:			79.70%		
Heat Transfer Efficiency:			82.02%		
Heat Output:	13149	BTU/Hr	13861 KJ/Hr		
Heat Input:	20115	BTU/Hr	21205 KJ/Hr		
Burn Duration:	1.95	Hours			
Burn Rate:	2.17	Lb/Hr	0.986 Kg/Hr		
Stack Temp:	229.1	Deg.F	109.5 Deg.C		
0.07064	0.14455518	#DIV/0!	#DIV/0!	2.34883	0.101
Comb %	Combust Eff %	Heat Transfer	Net Eff	air Fuel	Unit MN
K	%	Transfer	Eff		
0.37	86.2%	14.3%	12.4%	7	2.37
3.02	66.9%	64.4%	43.1%	5	1.72
4.61	63.7%	75.6%	48.1%	4	1.32
1.58	84.6%	84.4%	71.5%	5	0.91
0.65	90.4%	88.9%	80.4%	6	0.59
0.02	98.2%	91.6%	90.0%	12	0.32
-0.76	101.0%	90.5%	91.4%	17	0.27
-0.75	98.9%	91.7%	90.7%	17	0.23
-0.67	97.8%	92.3%	90.3%	19	0.18
-0.69	97.2%	92.9%	90.4%	21	0.14
-0.55	94.9%	93.5%	88.7%	23	0.09
-0.55	95.5%	93.8%	84.5%	26	0.05
-0.55	95.5%	94.2%	90.0%	29	0.00

Warnock Hersey Efficiency Test Report

Manufacturer:	Morso					
Model:	1410					
Date:	02/07/00					
Run:	3					
Control #:	31218					
Test Duration:	82					
	Start End					
Barometer (in.Hg):	29.34 29.4					
Wet Bulb (F):	56 59					
Dry Bulb (F):	70 80					
Humidity (%):	41 30					
Average Stove Temperature:	#DIV/0!					
Moisture content of wood (wet basis):	18.56					
Average:	1.267 10.32 9.459 317.9 73.7					
Elapsed Time:	Weight Remaining	CO	CO ₂	O ₂	Flue Gas	Room Temp
0	5.16	1.27	6.66	13.19	252	68
10	3.70	0.46	18.55	1.25	438	70
20	2.50	0.46	17.84	2.44	417	72
30	1.50	0.99	17.70	2.39	393	75
40	0.90	0.16	12.59	7.83	357	76
50	0.50	0.80	8.85	11.05	311	76
60	0.40	1.53	6.54	13.04	279	75
70	0.20	2.27	5.17	14.08	257	75
80	0.10	2.28	4.75	14.59	239	75
82	0.00	2.45	4.50	14.73	236	75


Overall Heating Efficiency:	65.52%				
Combustion Efficiency:	82.31%				
Heat Transfer Efficiency:	79.61%				
Heat Output:	18746 BTU/Hr	19762 KJ/Hr			
Heat Input:	28610 BTU/Hr	30159 KJ/Hr			
Burn Duration:	1.37 Hours				
Burn Rate:	3.07 Lb/Hr	1.395 Kg/Hr			
Stack Temp:	317.9 Deg.F	158.8 Deg.C			
0.05534 Comb %	0.10915354 Combust Eff %	#DIV/0! Heat Transfer	#DIV/0! Net Eff	2.1664 air Fuel	0.084 Unit MN
0.58	79.7%	10.8%	8.6%	8	2.34
3.19	72.5%	64.9%	47.0%	4	1.68
2.07	81.0%	77.4%	62.7%	5	1.13
0.44	93.0%	85.1%	79.2%	6	0.68
-0.35	104.5%	87.0%	90.9%	12	0.41
-0.57	106.7%	87.3%	93.2%	20	0.23
-0.43	98.5%	86.6%	85.3%	25	0.18
-0.25	86.8%	86.7%	75.3%	29	0.09
-0.11	82.0%	87.6%	57.6%	32	0.05
-0.09	79.5%	87.7%	69.7%	34	0.00

Manufacturer:	Morso					
Model:	1410					
Date:	02/08/00					
Run:	4					
Control #:	31218					
Test Duration:	65					
	Start	End				
Barometer (in.Hg):	29.4	29.38				
Wet Bulb (F):	52	56				
Dry Bulb (F):	68	76				
Humidity (%):	32	25				
Average Stove Temperature:	#DIV/0!					
Moisture content of wood (wet basis):	18.65					
	Average:	0.961	11.67	8.138	385.25	73.75
Elapsed:	Weight				Flue	Room
Time	Remaining	CO	CO ₂	O ₂	Gas	Temp
0	5.36	2.04	6.07	12.99	246	71
10	3.80	1.83	18.29	0.97	478	72
20	2.40	0.65	18.10	1.84	482	73
30	1.20	0.34	17.64	2.62	463	75
40	0.60	0.15	10.38	10.03	407	75
50	0.40	0.57	8.13	11.60	356	75
60	0.10	1.00	7.60	12.32	330	74
65	0.00	1.11	7.12	12.73	320	75

Warnock Hersey Efficiency Test Report

Overall Heating Efficiency:			66.79%		
Combustion Efficiency:			84.08%		
Heat Transfer Efficiency:			79.44%		
Heat Output:	25146	BTU/Hr	26508 KJ/Hr		
Heat Input:	37649	BTU/Hr	39689 KJ/Hr		
Burn Duration:	1.08	Hours			
Burn Rate:	4.02	Lb/Hr	1.826 Kg/Hr		
Stack Temp:	385.3	Deg.F	196.3 Deg.C		
0.04003	0.09399606	#DIV/0!	#DIV/0!	1.52788	0.078
Comb %	Combust Eff %	Heat Transfer	Net Eff	air Fuel	Unit MN
0.14	83.2%	13.1%	10.9%	8	2.43
3.89	65.9%	61.8%	40.7%	4	1.72
1.41	86.0%	77.6%	66.7%	5	1.09
-0.21	101.0%	85.4%	86.3%	8	0.54
-0.42	106.9%	84.9%	90.8%	17	0.27
-0.97	119.9%	84.7%	101.5%	25	0.18
-0.31	99.9%	86.4%	82.9%	27	0.05
-0.30	98.5%	86.5%	85.3%	30	0.00

APPENDIX J



0.1000°
 11,54 - 1-31-00 MORSO 2CM/HR

PRINTED IN U.S.A.

ORDER NO. 1865-45

100

G.C.I. - Farmer Instrument Company
 Chicago, Illinois 60648



PRINTED IN U.S.A.

